



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 8, 2011

SUBJECT: FAP Route 326 (IL 47)
Project ACNHF-0326 (083)
Section (5CS, 13C, 108, 109)R
Kendall County
Contract No. 66671
Item No. 95, November 18, 2011 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 6 and 14 of the Plans.
3. Revised pages iii and vi of the Table of Contents to the Special Provisions.
4. Revised pages 42 and 249 of the Special Provisions.
5. Added pages 258 - 259 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read 'Ted B. Walschleger', followed by the initials 'P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Eric Therkildsen, Region 2, District 3; Mike Renner; D.Carl Puzey;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MXK03460	LANDSCAPE RESTORATION	SQ M	489.000				
MX030063	STORM SEW WM REQ 300	METER	13.000				
MX030199	TEMP PAVEMENT	SQ M	6,138.000				
MX030203	TEMP PAVT REMOVAL	SQ M	6,138.000				
MX032179	SILICONE JT SEAL 25	METER	2.000				
MX032529	SEGMENT CONC BLK WALL	SQ M	28.700				
MX032821	WATER SERV CONN 30	EACH	1.000				
MX032822	WATER SERV CONN 50	EACH	2.000				
MX032842	BOX CULVERT REMOV	METER	106.000				
MX033775	WATER SERV CONN 25MM	EACH	21.000				
MX033830	TRENCH DRAIN 100	METER	40.000				
MX033832	CONCRETE COLOR ADDITIVE	CU M	239.000				
MX033834	REM REINST BRICK PAVR	SQ M	6.500				
MX356820	TEMP HMA BC WIDE 200	SQ M	5,904.000				
MX402045	AGG SURF CSE B 200	SQ M	218.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX420290	HES PCC DRWY PAVT 200	SQ M	185.000				
MX424005	PCC SIDEWALK SPL	SQ M	289.500				
MX424010	PCC SDWLK SPL RETWALL	SQ M	16.500				
MX440050	ISLAND PAVEMENT REM	SQ M	585.000				
MX440910	TEMP WIDENING REMOVAL	SQ M	5,904.000				
MX440950	HMA SURF REM VAR DP	SQ M	3,989.000				
MX481010	TEMP AGG WEDGE	M TON	10,795.000				
MX503020	ACCESS RAMP	CU M	21.200				
MX509035	DECORATIVE FENCE	METER	130.600				
MX509040	DECORATIVE HANDRAIL	METER	40.800				
MX509045	HANDRAIL	METER	61.600				
MX550506	CONNECT EX SEW <= 150	EACH	16.000				
MX550508	CONNECT EX SEWER 200	EACH	9.000				
MX550510	CONNECT EX SEWER 250	EACH	2.000				
MX550511	CONNECT EX SEWER 300	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX550512	SS ABAN 300	METER	50.000				
MX550515	SS ABAN 375	METER	81.000				
MX550518	SS ABAN 450	METER	16.000				
MX550521	SS ABAN 525	METER	40.000				
MX550536	SS ABAN 900	METER	320.000				
MX561068	WM CASING EXTEN 600	METER	18.000				
MX561315	TAP VALVE SLV 300X150	EACH	1.000				
MX561320	TAP VALVE SLV 300X200	EACH	1.000				
MX561704	LINE STOP 100	EACH	3.000				
MX561706	LINE STOP 150	EACH	5.000				
MX561708	LINE STOP 200	EACH	5.000				
MX561712	LINE STOP 300	EACH	4.000				
MX562020	WATER SERVICE COVER	EACH	5.000				
MX562140	WATER SERV CONNECT 40	EACH	4.000				
MX563306	SAN SEW PVC DR 18 150	METER	76.500				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX563308	SAN SEW PVC DR 18 200	METER	142.000				
MX563310	SAN SEW PVC DR 18 250	METER	10.500				
MX563408	SAN SEW PVC DR 21 200	METER	98.000				
MX563410	SAN SEW PVC DR 21 250	METER	62.000				
MX563412	SAN SEW PVC DR 21 300	METER	45.500				
MX563506	SAN SEW PVC SDR26 150	METER	43.500				
MX563508	SAN SEW PVC SDR26 200	METER	298.500				
MX563920	SAN SEW REPAIR 200	METER	9.500				
MX563950	TELEVISIONING SAN SEWER	METER	814.000				
MX602100	MAN A 2.4 DIA SPL	EACH	4.000				
MX602345	DROP MAN A SPL	EACH	1.000				
MX602490	SANITARY MANHOLE A	EACH	25.000				
MX604020	FRAMES & LIDS SPL	EACH	6.000				
MX606110	CONC CURB TB SPL	METER	125.100				
MX606320	CONC ISLAND SPL	SQ M	625.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX606360	COMB CC&G TB SPL	METER	9.200				
MX637005	CONCRETE BARRIER WALL	METER	132.000				
MX700005	STEEL SIGN SUPPRT SPL	METER	13.000				
MX780605	URETH PVT MK LTR-SYM	SQ M	398.000				
MX780610	URETH PVT MK LINE 100	METER	17,375.000				
MX780614	URETH PVT MK LINE 150	METER	6,732.000				
MX780616	URETH PVT MK LINE 200	METER	5,160.000				
MX780618	URETH PVT MK LINE 300	METER	2,102.000				
MX780622	URETH PVT MK LINE 600	METER	614.000				
MX783074	GRV RCSD PVT MRKG 178	METER	2,431.000				
MX836021	LT P FDN 750 DIA SPL	METER	126.000				
MX836022	LP FDN 750 D SPL MOD	METER	6.000				
MX871057	FOCC62.5/125 MM24SM24	METER	5,079.000				
MX873025	ELCBL C RAILRD 14 3C	METER	123.000				
MX873030	ELCBL C 20 3C TW SH	METER	5,356.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MX877020	STL COMB MAA&P 16.76	EACH	1.000				
MX878020	CONC FDN TY C SPL	METER	9.900				
MX878030	CONC FDN TY E 900D	METER	102.000				
MZ001050	AGG SUBGRADE 300	SQ M	95,048.000				
MZ001080	AGG SUBGRADE 600	SQ M	54,432.000				
MZ007430	TEMP SIDEWALK	SQ M	400.000				
MZ016001	DECK SLAB REP (FD-T1)	SQ M	22.000				
MZ016002	DECK SLAB REP (FD-T2)	SQ M	37.000				
MZ023500	FILL EXIST CULVERTS	CU M	31.400				
MZ067000	STEEL CASINGS 150	METER	66.000				
MZ067700	STEEL CASINGS 500	METER	402.000				
MZ067800	STEEL CASINGS 550	METER	39.000				
MZ067900	STEEL CASINGS 600	METER	81.000				
MZ068200	STEEL CASINGS 750	METER	29.000				
MZ068450	STEEL CASINGS 1650	METER	56.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
MZ075498	CONC RETAIN WALL REM	METER	161.000				
M2010110	TREE REMOV 6-15	UNIT	1,346.000				
M2010210	TREE REMOV OVER 15	UNIT	1,548.000				
M2011000	TEMPORARY FENCE	METER	24.000				
M2011400	NITROGEN FERT NUTR	KG	1.000				
M2011500	PHOSPHORUS FERT NUTR	KG	1.000				
M2011600	POTASSIUM FERT NUTR	KG	1.000				
M2020010	EARTH EXCAVATION	CU M	86,200.000				
M2020020	ROCK EXCAVATION	CU M	404.000				
M2020050	EARTH EXC WID	CU M	1,181.000				
M2080150	TRENCH BACKFILL	CU M	24,153.000				
M2090110	POROUS GRAN BACKFILL	CU M	8.000				
M2113100	TOPSOIL F & P 100	SQ M	65,969.000				
M2113600	TOPSOIL F & P 600	SQ M	1,163.000				
M2130201	EXPLOR TRENCH 2.1	METER	67.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M2500100	SEEDING CL 1	HA	6.000				
M2500210	SEEDING CL 2A	HA	0.500				
M2500400	NITROGEN FERT NUTR	KG	648.000				
M2500500	PHOSPHORUS FERT NUTR	KG	648.000				
M2500600	POTASSIUM FERT NUTR	KG	648.000				
M2510630	EROSION CONTR BLANKET	SQ M	64,806.000				
M2800250	TEMP EROS CONTR SEED	KG	713.000				
M2800305	TEMP DITCH CHECKS	METER	273.000				
M2800400	PERIMETER EROS BAR	METER	5,725.000				
M2800800	MULCH METHOD 2	HA	6.500				
M2810109	STONE RIPRAP CL A5	SQ M	219.000				
M2820200	FILTER FABRIC	SQ M	219.000				
M3112010	SUB GRAN MAT C	M TON	459.000				
M3510100	AGG BASE CSE A 100	SQ M	9,158.000				
M3510200	AGG BASE CSE A 200	SQ M	2,266.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M3511150	AGG BASE CSE B 150	SQ M	11,521.000				
M3540200	PCC BASE CSE W 200	SQ M	94.000				
M3550415	HMA BASE CSE 115	SQ M	2,038.000				
M3560570	HMA BC WID 270	SQ M	783.000				
M4021200	AGGREGATE-TEMP ACCESS	M TON	4,161.000				
M4060100	BIT MATLS PR CT	LITER	10,812.000				
M4060300	AGG PR CT	M TON	19.000				
M4060982	HMA SURF REM BUTT JT	SQ M	146.000				
M4060990	TEMPORARY RAMP	SQ M	976.000				
M4062325	P LEV BIND MM N50	M TON	298.000				
M4063305	HMA SC "C" N30	M TON	1,610.000				
M4063345	HMA SC "D" N90	M TON	449.000				
M4063370	HMA SC "E" N90	M TON	250.000				
M4080100	BIT MATLS PR CT	LITER	3,956.000				
M4080300	AGG PR CT	M TON	4.200				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M4080500	INCIDENTAL HMA SURF	M TON	610.000				
M4202255	PCC PVT 250 JOINTED	SQ M	129,099.000				
M4205100	PAVEMENT FABRIC	SQ M	1,181.000				
M4230150	PCC DRIVEWAY PAVT 150	SQ M	2,125.000				
M4230200	PCC DRIVEWAY PAVT 200	SQ M	5,474.000				
M4240100	PC CONC SIDEWALK 100	SQ M	9,361.000				
M4248000	DETECTABLE WARNINGS	SQ M	299.700				
M4400738	HMA SURF REM 38	SQ M	614.000				
M4402000	PAVEMENT REM	SQ M	102,652.000				
M4402010	DRIVE PAVEMENT REM	SQ M	14,505.000				
M4402020	CURB REM	METER	655.000				
M4402030	GUTTER REM	METER	18.000				
M4402040	COMB CURB GUTTER REM	METER	5,920.000				
M4402050	SIDEWALK REM	SQ M	4,529.000				
M4402420	MEDIAN REMOVAL	SQ M	1,290.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER -

66671

State Job # - C-93-064-05
PPS NBR - 3-02970-0100
County Name - KENDALL - -
Code - 93 - -
District - 3 - -
Section Number - (5CS,13C,108,109)R

Project Number
ACNHF-0326/083/

Route
FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M4405000	PAVED DITCH REMOVAL	METER	207.000				
M4422200	PAVT PATCH T2 200	SQ M	29.000				
M4423200	PAVT PATCH T3 200	SQ M	21.000				
M4424200	PAVT PATCH T4 200	SQ M	203.000				
M4427415	CL C PATCH T4 200	SQ M	66.000				
M4428404	CL D PATCH T4 100	SQ M	89.000				
M4428410	CL D PATCH T4 150	SQ M	394.000				
M4428440	CL D PATCH T4 300	SQ M	94.000				
M4430020	STRIP REF CR CON TR	METER	413.000				
M4812150	AGGREGATE SHLDS B 150	SQ M	126.000				
M4820600	HMA SHOULDERS 200	SQ M	138.000				
M4820650	HMA SHOULDERS 250	SQ M	439.000				
M5010240	CONC REM	CU M	11.000				
M5010522	PIPE CULVERT REMOV	METER	883.000				
M5020400	ROCK EXC STRUCT	CU M	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5030290	FORM LINER TEX SURF	SQ M	3.400				
M5030360	CONC SUP-STR	CU M	11.100				
M5080205	REINF BARS, EPOXY CTD	KG	970.000				
M5090540	PIPE HANDRAIL	METER	54.200				
M5200225	PREF JT STRIP SEAL	METER	45.000				
M542A100	GRAT-C FL END S 375	EACH	2.000				
M542A110	GRAT-C FL END S 450	EACH	2.000				
M542C656	RCP TEE 1350P 900R	EACH	1.000				
M542E112	PRC FL-END SEC 300	EACH	9.000				
M542E116	PRC FL-END SEC 375	EACH	2.000				
M542E120	PRC FL-END SEC 450	EACH	6.000				
M542F252	CIP RC END SEC 1200	EACH	2.000				
M542H025	P CUL CL A 1 375	METER	20.500				
M542H030	P CUL CL A 1 450	METER	9.500				
M5500215	STORM SEW CL B 1 150	METER	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5500300	STORM SEW CL B 1 1200	METER	80.000				
M5505530	SS RG CL A 1 300	METER	2,734.000				
M5505550	SS RG CL A 1 450	METER	442.000				
M5505570	SS RG CL A 1 600	METER	142.500				
M5505590	SS RG CL A 1 750	METER	190.500				
M5505610	SS RG CL A 1 900	METER	59.000				
M5505620	SS RG CL A 1 1050	METER	137.000				
M5505630	SS RG CL A 1 1200	METER	68.000				
M5505640	SS RG CL A 1 1350	METER	243.000				
M5505930	SS RG CL A 2 300	METER	1,255.000				
M5505950	SS RG CL A 2 450	METER	830.000				
M5505970	SS RG CL A 2 600	METER	634.000				
M5505990	SS RG CL A 2 750	METER	514.500				
M5506010	SS RG CL A 2 900	METER	858.500				
M5506020	SS RG CL A 2 1050	METER	965.500				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5506030	SS RG CL A 2 1200	METER	810.000				
M5506040	SS RG CL A 2 1350	METER	185.000				
M5506050	SS RG CL A 2 1500	METER	426.500				
M5506060	SS RG CL A 2 1650	METER	193.000				
M5506330	SS RG CL A 3 300	METER	15.000				
M5506420	SS RG CL A 3 1050	METER	54.500				
M5506430	SS RG CL A 3 1200	METER	424.500				
M5510005	STORM SEWER REM 100	METER	7.000				
M5510010	STORM SEWER REM 150	METER	20.000				
M5510015	STORM SEWER REM 200	METER	54.000				
M5510020	STORM SEWER REM 250	METER	79.000				
M5510025	STORM SEWER REM 300	METER	1,143.000				
M5510035	STORM SEWER REM 375	METER	659.000				
M5510045	STORM SEWER REM 450	METER	406.000				
M5510060	STORM SEWER REM 600	METER	154.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5510070	STORM SEWER REM 750	METER	334.000				
M5510080	STORM SEWER REM 900	METER	463.000				
M5510100	STORM SEWER REM 1350	METER	6.000				
M5610415	D I WATER MAIN 150	METER	3.000				
M5610420	D I WATER MAIN 200	METER	1,654.500				
M5610430	D I WATER MAIN 300	METER	527.000				
M5610635	WATER VALVES 150	EACH	2.000				
M5610640	WATER VALVES 200	EACH	21.000				
M5610650	WATER VALVES 300	EACH	5.000				
M5611205	TAP VALVE & SLVE 100	EACH	5.000				
M5611210	TAP VALVE & SLVE 150	EACH	4.000				
M5611215	TAP VALVE & SLVE 200	EACH	5.000				
M5611225	TAP VALVE & SLVE 300	EACH	3.000				
M5620115	WATER SERV LINE 25	METER	259.000				
M5620120	WATER SERV LINE 30	METER	9.500				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M5620130	WATER SERV LINE 40	METER	70.000				
M5620135	WATER SERV LINE 50	METER	34.000				
M6010105	PIPE DRAINS 100	METER	17.500				
M6010110	PIPE DRAINS 150	METER	6.500				
M6010115	PIPE DRAINS 200	METER	87.500				
M6010605	PIPE UNDERDRAINS 100	METER	753.500				
M6010705	PIPE UNDERDRN 100 SP	METER	134.500				
M6020417	CB A 1.5M D T3V F&G	EACH	1.000				
M6020651	CB A 1.8M D T5F CL	EACH	2.000				
M6020701	CB A 2.1M D T1F CL	EACH	1.000				
M6021410	MAN A 1.2D T1F CL	EACH	47.000				
M6021417	MAN A 1.2D T3VF&G	EACH	32.000				
M6021430	MAN A 1.2D T5F CL	EACH	12.000				
M6021440	MAN A 1.2D T8G	EACH	16.000				
M6021457	MAN A 1.2D T11V F&G	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M6021470	MAN A 1.2D T20F&G	EACH	2.000				
M6021610	MAN A 1.5D T1F CL	EACH	29.000				
M6021617	MAN A 1.5D T3VF&G	EACH	10.000				
M6021630	MAN A 1.5D T5F CL	EACH	5.000				
M6021640	MAN A 1.5D T8G	EACH	11.000				
M6021657	MAN A 1.5M D T11V F&G	EACH	2.000				
M6021810	MAN A 1.8D T1F CL	EACH	31.000				
M6021830	MAN A 1.8D T5F CL	EACH	5.000				
M6021840	MAN A 1.8D T8G	EACH	5.000				
M6022010	MAN A 2.1D T1F CL	EACH	25.000				
M6022075	MAN A 2.1 DIA T3V F&G	EACH	1.000				
M6022090	MAN A 2.4D T1F CL	EACH	5.000				
M6022111	MAN A 2.4 D T11V F&G	EACH	1.000				
M6022152	MAN A 2.4 DIA T5F CL	EACH	9.000				
M6022188	MAN A 2.4 DIA T8 GR	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M6022352	MAN A 2.7 DIA T5F CL	EACH	1.000				
M6022388	MAN A 2.7 DIA T8 GR	EACH	3.000				
M6024310	VV TA 1.2MD T1F CL	EACH	21.000				
M6024410	VV TA 1.5MD T1F CL	EACH	18.000				
M6060070	CONC CURB TB	METER	24.500				
M6060500	COMB CC&G TB15.30	METER	19.200				
M6060505	COMB CC&G TB15.30 AEP	METER	31.500				
M6060510	COMB CC&G TB15.30 DOW	METER	2,566.600				
M6060610	COMB CC&G TB15.45 DOW	METER	53.000				
M6060700	COMB CC&G TB15.60	METER	87.900				
M6060705	COMB CC&G TB15.60 AEP	METER	20.600				
M6060710	COMB CC&G TB15.60 DOW	METER	11,311.100				
M6061940	COMB CC&G TM10.30 DOW	METER	21.900				
M6063700	CONC MED TM-5	SQ M	632.000				
M6064110	CONC MED TSB15.30 DOW	SQ M	354.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M6064210	CONC MED TSB15.60 DOW	SQ M	995.000				
M6066010	CORRUGATED MED DOW	SQ M	168.000				
** REV M6690200	NON SPL WASTE DISPOSL	CU M	620.000				
M7030510	PAVT MARK TAPE T3 L&S	SQ M	422.000				
M7030520	PAVT MARK TAPE T3 100	METER	103,564.000				
M7030540	PAVT MARK TAPE T3 150	METER	1,988.000				
M7030550	PAVT MARK TAPE T3 200	METER	5,878.000				
M7030560	PAVT MARK TAPE T3 300	METER	1,234.000				
M7030580	PAVT MARK TAPE T3 600	METER	1,133.000				
M7031000	WORK ZONE PAVT MK REM	SQ M	13,811.000				
M7040100	TEMP CONC BARRIER	METER	666.000				
M7040200	REL TEMP CONC BARRIER	METER	446.000				
M7200100	SIGN PANEL T1	SQ M	140.820				
M7200200	SIGN PANEL T2	SQ M	70.720				
M7280100	TELES STL SIN SUPPORT	METER	64.300				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M7300100	WOOD SIN SUPPORT	METER	845.200				
M8100230	CON T 25 PVC	METER	1,464.000				
M8100240	CON T 30 PVC	METER	109.000				
M8100260	CON T 50 PVC	METER	4,834.000				
M8100270	CON T 65 PVC	METER	15.000				
M8100280	CON T 75 PVC	METER	75.000				
M8100300	CON T 100 PVC	METER	454.000				
M8100540	CON T 50 CNC	METER	2,541.000				
M8101020	CON P 25 GALVS	METER	25.000				
M8101050	CON P 50 GALVS	METER	925.000				
M8101070	CON P 75 GALVS	METER	57.000				
M8101090	CON P 100 GALVS	METER	774.000				
M8101850	CON B&P CNC 50	METER	111.000				
M8170020	EC C XLP USE 1C 10	METER	5,578.000				
M8170040	EC C XLP USE 1C 6	METER	13,811.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M8190200	TR & BKFIL F ELECT WK	METER	9,235.000				
M8730925	ELCBL C TRACER 14 1C	METER	5,079.000				
M8731210	ELCBL C SIGNAL 14 2C	METER	4,136.000				
M8731220	ELCBL C SIGNAL 14 3C	METER	3,691.000				
M8731240	ELCBL C SIGNAL 14 5C	METER	7,146.000				
M8731250	ELCBL C SIGNAL 14 7C	METER	4,148.000				
M8731300	ELCBL C LEAD 14 1PR	METER	17,710.000				
M8731800	ELCBL C SERV 6 2C	METER	141.000				
M8750510	TS POST GALVS 4.85	EACH	26.000				
M8770725	STL COMB MAA&P 7.31	EACH	2.000				
M8770755	STL COMB MAA&P 10.97	EACH	1.000				
M8770760	STL COMB MAA&P 11.58	EACH	3.000				
M8770765	STL COMB MAA&P 12.19	EACH	1.000				
M8770770	STL COMB MAA&P 12.80	EACH	1.000				
M8770775	STL COMB MAA&P 13.41	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M8770777	STL COMB MAA&P 14.02	EACH	3.000				
M8770779	STL COMB MAA&P 14.63	EACH	5.000				
M8770780	STL COMB MAA&P 15.24	EACH	6.000				
M8770782	STL COMB MAA&P 15.85	EACH	2.000				
M8770784	STL COMB MAA&P 16.46	EACH	1.000				
M8770790	STL COMB MAA&P 18.29	EACH	2.000				
M8770800	STL COMB MAA&P 21.34	EACH	1.000				
M8770803	STL COMB MAA&P 22.56	EACH	1.000				
M8770804	STL COMB MAA&P 22.86	EACH	3.000				
M8780100	CONC FDN TY A	METER	32.900				
M8780150	CONC FDN TY C	METER	1.200				
M8780200	CONC FDN TY D	METER	1.800				
M8780400	CONC FDN TY E 750D	METER	6.000				
M8780420	CONC FDN TY E 1060D	METER	57.800				
M8860100	DET LOOP T1	METER	5,839.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
M8950230	REM ELCBL FR CON	METER	250.000				
M8950235	REM & RE ELCBL FR CON	METER	250.000				
XX002856	RE-OPTIMIZE TR SIG SY	L SUM	1.000				
XX004360	SAN SEW BYPASS PUMP	L SUM	1.000				
XX104100	CONN EX MANHOLE	EACH	1.000				
XZ053750	APPR PARAPE RETRO SPL	EACH	2.000				
X0322215	CLEAN BRG SCUP/DWNSPT	EACH	22.000				
X0322719	TEMP DRAINAGE CONNECT	EACH	2.000				
X5030015	OUTLET STRUCTURE	L SUM	1.000				
X5630905	TEMP INVERTED SIPHON	EACH	1.000				
X6020074	INLETS TA T3V F&G	EACH	160.000				
X6020075	INLETS TB T3V F&G	EACH	142.000				
X6021193	TEMP CATCH BASINS	EACH	12.000				
X6024207	MED INLET (604106) SP	EACH	1.000				
X6026050	SANITARY MANHOLE ADJ	EACH	21.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6026622	VV REMOVED	EACH	21.000				
X6026623	VALVE BOX	EACH	8.000				
X6026632	VALVE BOX REMOVED	EACH	15.000				
X6029001	JUNCTION BOX N1	L SUM	1.000				
X6029002	JUNCTION BOX N2	L SUM	1.000				
X6029003	JUNCTION BOX N3	L SUM	1.000				
X6029004	JUNCTION BOX N4	L SUM	1.000				
X6029005	JUNCTION BOX N5	L SUM	1.000				
X6310218	TRAF BAR TERM T6 SPL	EACH	2.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7011010	TR C-PROT STAGE CONST	L SUM	1.000				
X8000005	WIRELESS LI PED X SYS	L SUM	1.000				
X8130125	REM EX JUNCTION BOX	EACH	7.000				
X8250505	LIGHT CONTROLLER SPL	EACH	9.000				
X8360120	LIGHT POLE FDN SPL	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X8510200	PAINT TRAF SIG EQUIP	L SUM	1.000				
X8570225	FAC T4 CAB SPL	EACH	8.000				
X8570230	FAC T5 CAB SPL	EACH	2.000				
X8900016	TEMP TRAF SIG INTERCONNECT SYS	EACH	1.000				
X8900017	TEMP TRAF SIG INTERCONNECT SYS	EACH	1.000				
X8900018	TEMP TRAFSIG INTER S3	EACH	1.000				
X8950114	MOD EX CONTR & CAB	EACH	9.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0007602	BLDG REMOV NO 2	L SUM	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0016702	DETOUR SIGNING	L SUM	1.000				
Z0026346	NIGHT WORK ZONE LIGHT	L SUM	1.000				
Z0030260	IMP ATTN TEMP FRN TL3	EACH	6.000				
Z0030332	IMP ATTN REL FRN TL3	EACH	8.000				
Z0033047	TEMP REOPT EX TS SYS	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0049802	R&D FRIABL ASB BLD 2	L SUM	1.000				
*ADD Z0049902	R&D NON-FR ASB BLD 2	L SUM	1.000				
Z0053610	RECONSTRUCT BENCH	EACH	2.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	12.000				
*ADD Z0076600	TRAINEES	HOUR	2,500.000		0.800		2,000.000
20101200	TREE ROOT PRUNING	EACH	1.000				
28000500	INLET & PIPE PROTECT	EACH	531.000				
50104400	CONC HDWL REM	EACH	3.000				
56400100	FIRE HYDNPTS TO BE MVD	EACH	2.000				
56400300	FIRE HYDNPTS TO BE ADJ	EACH	6.000				
56400500	FIRE HYDNPTS TO BE REM	EACH	21.000				
56400600	FIRE HYDRANTS	EACH	29.000				
56500600	DOM WAT SER BOX ADJ	EACH	2.000				
56500700	DOM WAT SER BOX REM	EACH	39.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60236200	INLETS TA T8G	EACH	41.000				
60236825	INLETS TA T11V F&G	EACH	30.000				
60237420	INLETS TA T20F&G	EACH	1.000				
60240210	INLETS TB T1F OL	EACH	1.000				
60240215	INLETS TB T1F CL	EACH	7.000				
60240235	INLETS TB T5F CL	EACH	1.000				
60240301	INLETS TB T8G	EACH	13.000				
60240312	INLETS TB T11V F&G	EACH	38.000				
60240324	INLETS TB T20F&G	EACH	1.000				
60265700	VV ADJUST	EACH	16.000				
60266100	VV RECONST	EACH	1.000				
60266600	VALVE BOX ADJ	EACH	8.000				
60500040	REMOV MANHOLES	EACH	72.000				
60500050	REMOV CATCH BAS	EACH	16.000				
60500060	REMOV INLETS	EACH	87.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011

** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60500105	FILL MANHOLES	EACH	13.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	2.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
** REV 66900530	SOIL DISPOSAL ANALY	EACH	9.000				
67000400	ENGR FIELD OFFICE A	CAL MO	32.000				
67100100	MOBILIZATION	L SUM	1.000				
*ADD 67201100	SEAL ABAN MONIT WELLS	EACH	2.000				
70103815	TR CONT SURVEILLANCE	CAL DA	600.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	120.000				
78100100	RAISED REFL PAVT MKR	EACH	1,993.000				
78200300	PRISMATIC CURB REFL	EACH	372.000				
78200410	GUARDRAIL MKR TYPE A	EACH	2.000				
78201000	TERMINAL MARKER - DA	EACH	2.000				
80400100	ELECT SERV INSTALL	EACH	1.000				
80500010	SERV INSTALL GRND MT	EACH	20.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81400700	HANDHOLE PCC	EACH	90.000				
81400720	DBL HANDHOLE PCC	EACH	9.000				
81400730	HANDHOLE C CONC	EACH	17.000				
82102250	LUM SV HOR MT 250W	EACH	12.000				
82102400	LUM SV HOR MT 400W	EACH	23.000				
82500330	LT CONT PEDM 240V 60	EACH	1.000				
84200500	REM LT UNIT SALV	EACH	17.000				
84200804	REM POLE FDN	EACH	14.000				
84500110	REMOV LIGHTING CONTR	EACH	1.000				
84500120	REMOV ELECT SERV INST	EACH	1.000				
85000200	MAIN EX TR SIG INSTAL	EACH	19.000				
86000100	MASTER CONTROLLER	EACH	2.000				
86200300	UNINTER POWER SUP EXT	EACH	10.000				
86400100	TRANSCEIVER - FIB OPT	EACH	14.000				
87601100	PED P-B POST GALVS T1	EACH	6.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87900200	DRILL EX HANDHOLE	EACH	3.000				
88040070	SH P LED 1F 3S BM	EACH	33.000				
88040090	SH P LED 1F 3S MAM	EACH	72.000				
88040150	SH P LED 1F 5S BM	EACH	39.000				
88040160	SH P LED 1F 5S MAM	EACH	24.000				
88102810	PED SH P LED 1F BM	EACH	8.000				
88102825	PED SH P LED 1F BM CT	EACH	60.000				
88200410	TS BACKPLATE L F PLAS	EACH	168.000				
88500100	INDUCTIVE LOOP DETECT	EACH	127.000				
88700200	LIGHT DETECTOR	EACH	35.000				
88700300	LIGHT DETECTOR AMP	EACH	9.000				
88800100	PED PUSH-BUTTON	EACH	76.000				
89000100	TEMP TR SIG INSTALL	EACH	9.000				
89502210	MOD EX CONTR CAB	EACH	2.000				
89502375	REMOV EX TS EQUIP	EACH	10.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 66671

State Job # - C-93-064-05
 PPS NBR - 3-02970-0100
 County Name - KENDALL - -
 Code - 93 - -
 District - 3 - -
 Section Number - (5CS,13C,108,109)R

Project Number
 ACNHF-0326/083/

Route
 FAP 326

* REVISED: NOVEMBER 07, 2011
 ** REVISED: NOVEMBER 17, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89502380	REMOV EX HANDHOLE	EACH	69.000				
89502385	REMOV EX CONC FDN	EACH	68.000				

TAPPING VALVES AND SLEEVES 32

VALVE VAULTS..... 32

VALVE BOX 32

FIRE HYDRANT 32

FIRE HYDRANT TO BE ADJUSTED..... 33

FIRE HYDRANT TO BE REMOVED 33

LINE STOP 33

WATER SERVICE LINE 34

WATER SERVICE CONNECTION 34

WATER SERVICE COVER..... 34

WATERMAIN ABANDONMENT 35

VALVE VAULTS TO BE REMOVED 35

VALVE BOXES TO BE REMOVED 35

DOMESTIC WATER SERVICE BOXES TO BE REMOVED..... 35

DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED..... 36

LANDSCAPE RESTORATION 36

MEDIAN INLET (604106), SPECIAL 36

PIPE UNDERDRAINS 100MM 36

PIPE UNDERDRAINS 100MM (SPECIAL)..... 37

MANHOLES, TYPE A 37

MANHOLES, TYPE A, 2.4M DIAMETER, SPECIAL 37

INLETS, TYPE B..... 38

TRENCH DRAIN, 100MM 38

TEMPORARY CATCH BASINS..... 38

CONCRETE ISLAND (SPECIAL) 39

CONCRETE CURB, TYPE B (SPECIAL) 39

COMBINATION CONCRETE CURB AND GUTTER (ABUTTING EXISTING PAVEMENT) 39

COMBINATION CONCRETE CURB AND GUTTER (DOWELLED) 39

COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL) 40

CONCRETE MEDIAN (DOWELLED) 40

CORRUGATED MEDIAN (DOWELLED)..... 40

JUNCTION BOX 40

OUTLET STRUCTURE..... 41

TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL) 41

CONCRETE BARRIER WALL 42

HOURS OF OPERATION / KEEPING ROADS OPEN TO TRAFFIC 42

Revised 11/17/2011

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 139

NIGHTTIME WORK ZONE LIGHTING (BDE) 140

PAVEMENT MARKING REMOVAL (BDE) 142

PAVEMENT PATCHING (BDE) 142

PAYMENTS TO SUBCONTRACTORS (BDE) 142

POST MOUNTING OF SIGNS (BDE)..... 143

PRECAST CONCRETE HANDLING HOLES (BDE) 144

RAISED REFLECTIVE PAVEMENT MARKERS (BDE) 145

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 145

SEEDING (BDE) 152

SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE)..... 154

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE) 158

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 159

SURFACE TESTING OF PAVEMENTS (BDE) 159

TEMPORARY EROSION CONTROL (BDE) 165

TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE) 168

TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 169

TRAFFIC CONTROL SURVEILLANCE (BDE) 169

UTILITY COORDINATION AND CONFLICTS (BDE)..... 169

WORKING DAYS (BDE) 174

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 174

STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 177

PROJECT LABOR AGREEMENT 181

STORM WATER POLLUTION PREVENTION PLAN..... 194

404 PERMIT 205

NATIONWIDE PERMITS AND CONDITIONS..... 208

IEPA REGIONAL CONDITIONS..... 221

TRAINING SPECIAL PROVISIONS (BDE) 239

BUILDING REMOVAL NO. 1 242

BUILDING REMOVAL NO. 2 242

BUILDING REMOVAL - CASE I (NON-FRIABLE AND FRIABLE ASBESTOS ABATEMENT) (BDE)..... 242

BUILDING REMOVAL - CASE IV (NO ASBESTOS)..... 253

TIE BAR INSERTER 254

DOWEL BAR INSERTER 255

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 258

CONCRETE BARRIER WALL

This item of work shall consist of furnishing and installing a reinforced concrete barrier wall at the locations shown in the plans in accordance with applicable portions of Section 637 and reinforcement bars shall be in accordance with applicable portions of Section 508 of the Standard Specifications, the details shown in the plans, and as modified herein.

This item shall be measured for payment along the centerline of the barrier wall in meters.

All labor, equipment and materials required to complete this item as specified herein, including excavation, formwork, Class SI concrete, reinforcement bars, etc., will be paid for at the contract unit price per meter for CONCRETE BARRIER WALL.

HOURS OF OPERATION / KEEPING ROADS OPEN TO TRAFFIC

All work, including the installation and removal of all traffic control protection, which requires the closing of a driving lane of Illinois Route 47 shall be performed nightly between the hours of 8 p.m. and 6 a.m. Night time lane closures will only be allowed Sunday night through Friday night. Work not requiring lane closures shall also be permitted during these hours. However, slamming of delivery truck tail gates and using milling machines or jackhammers of any size will not be permitted during these hours. The contractor shall abide by the noise requirements set forth in Article 107.35 of the Standard Specifications. The Engineer reserves the right to reject equipment and/or operations that causes excessive noise during the hours of 8 p.m. and 6 a.m.

The Contractor shall notify the Yorkville Police Department and residents within a two block area of proposed night time work location at least 24 hours before the work commences along with an estimate of how long work shall last.

All Illinois Route 47 driving lanes shall be open to traffic during the legal holiday periods according to Article 107.09 of the Standard specifications.

No additional compensation will be allowed the Contractor for working at night, except as outlined in the special provision, Nighttime Work Zone Lighting.

TRAFFIC CONTROL AND PROTECTION (SPECIAL)

This item of work shall include installation, maintenance, and removal of any measures required to maintain pedestrian traffic to buildings (such as those between Van Emmon Street and Hydraulic Avenue) during construction in accordance with Section 701 and as detailed in the plans.

Revised 11/17/2011

APPENDIX A

MATERIAL DESCRIPTION TABLE

Material Description	% And Type Of Asbestos	Location, Description, Sample Number (If Applicable)
I. <u>301 S Bridge St (Sta. 20+816 LT)</u>		
Exterior Window Glazing	4% Chrysotile	2 nd Floor windows (Southside) Poor condition. Friable. Sample 11-35.
Gray, Fibrous Paper	40% chrysotile	2 nd floor. At center exterior in small opening on east wall on door. Poor condition. Sample 14-44. Non-friable
Flat Tar Buildup Roofing		Upper roof. Assumed. Non-friable.
Roof Flashing		Upper roof. Assumed. Non-friable.

APPENDIX B

MATERIAL QUANTITIES TABLE

The following are approximate quantities of ACM to be removed from the building indicated. These material quantities do not indicate the cleaning required to remove asbestos debris and resulting contamination from the work areas.

I. 301 S Bridge St (Sta. 20+816 LT)

<u>Material</u>	<u>Floor</u>	<u>Quantity Present</u>	<u>Friable</u>
Window Glazing	2 nd Floor	5 S.F. (0.46 SM)	Yes
Gray Paper	2 nd Floor	2 S.F. (0.19 SM)	No
Roof Flashing	Upper Roof	110 L.F. (33.5 L.M.)	No
Flat Tar Buildup Roofing	Upper Roof	1475 S.F. (137 S.M.)	No

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities. .

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances.

A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage and dispose of all soils excavated within the following areas as classified below. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less. Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. Phase I Preliminary Engineering information is available through the District's Environmental Studies Unit.

1. Station 50+035 to Station 50+075 0 to 15 meters (0 to 49 feet) RT (State Bank of Yorkville, Site 504I-65, 28 Schoolhouse Road) – non-special waste. Contaminants of concern sampling parameters: PNAs.
2. Station 20+580 to Station 20+635 0 to 15 meters (0 to 49 feet) RT (Speedway Gas, Site 504I-56, 504 South Bridge Street) – non-special waste. Contaminants of concern sampling parameters: Lead, Arsenic, and Mercury.
3. Station 189+930 to Station 189+965 0 to 15 meters (0 to 49 feet) RT (Walgreens, Site 504I-20, 152 West Veterans Parkway) – non-special waste. Contaminants of concern sampling parameters: PNAs.
4. Station 22+735 to Station 22+780 0 to 35 meters (0 to 115 feet) LT (Shell, Site 504I-13, 1421 North Bridge Street) – non-special waste. Contaminants of concern sampling parameters: Lead.
5. Station 190+110 to Station 190+145 0 to 25 meters (0 to 82 feet) LT(Commercial Building, Site 504I-16, 197-201 East Veterans Parkway) – non-special waste. Contaminants of concern sampling parameters: PNAs.

B) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill**. Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property.

All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.

1. Station 18+900 to Station 18+930 0 to 20 meters (0 to 66 feet) LT and RT (Ground Effect, Site 504I-74, 1801 South Bridge Street) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
2. Station 50+015 to Station 50+090 0 to 30 meters (0 to 98 feet) LT (Vacant Building, Site 504I-63, 1002 South Bridge Street) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
3. Station 20+830 to Station 20+875 0 to 15 meters (0 to 49 feet) RT (Kendall County Record, Site 504I-47, 222 South Bridge Street) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
4. Station 20+940 to Station 20+965 0 to 15 meters (0 to 49 feet) RT (Bridge Street, Site 504I-1) – non-special waste. Contaminants of concern sampling parameters: Mercury.