

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109)R	KENDALL	931	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SPEC. PROV.	SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%		FEDERAL = 80%							FEDERAL=80%	FEDERAL=80%	FEDERAL = 0%			
						STATE = 20%		STATE = 10%							STATE=0%	STATE=0%	STATE = 0%			
						CITY=0%		CITY = 10%							CITY=20%	CITY=20%	CITY = 100%			
						ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONIAK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)	ROADWAY (SOMONIAK STREET)	SAFETY AND LIGHTING
0003	0014	0021		0021							0028	0021	0003	0021	0031	0043				
01	01	01	02	03	04	05	06	07	08	09	01	10	01	01	01	01				
#		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2														
*		66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1														
*		66900530	SOIL DISPOSAL ANALYSIS	EACH	9	9														
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	32	32														
		67100100	MOBILIZATION	L SUM	1	1														
		67201100	SEALING ABANDONED MONITORING WELLS	EACH	2	2														
		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	600	600														
*		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	120	120														
		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,993	1,993														
		78200300	PRISMATIC CURB REFLECTOR	EACH	372	372														
		78200410	GUARDRAIL MARKERS, TYPE A	EACH	2	2														
		78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2														
*		80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1														
*	*	80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	20	2		2	2	2	2	2	2	2						
		81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	90	41		6	7	7	5	6	5	5	5	3				
		81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	9			1	1	1	1	1	1	1	1					
		81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	17												17			
*		82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12												12			
*		82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	23												23			
*		82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1	1														
		84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	17	14											3			
		84200804	REMOVAL OF POLE FOUNDATION	EACH	14	14														
*		84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1														
*		84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1														
*	*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	19	19														

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS	
NAME	DATE
BDD	9/1/11

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 DATE _____ DRAWN BY _____
 CHECKED BY _____

FILE: \$FILE\$
 PLOTTED: 9/1/2011

Rev. 11-17-11 Rev. 11-7-11

HMG 029 NO. 5122

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%				FEDERAL = 80%				FEDERAL=80%	FEDERAL = 0%			
					STATE = 20%				STATE = 10%				STATE=0%	STATE = 0%			
					CITY=0%				CITY = 10%				CITY=20%	CITY = 100%			
					ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)
0003	0014	0021		0021						0028	0021	0003	0021	0031	0043		
*	M6021630	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 5 FRAME, CLOSED LID	EACH	5	5												
*	M6021640	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 8 GRATE	EACH	11	11												
*	M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	31	31												
*	M6021830	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 5 FRAME, CLOSED LID	EACH	5	5												
*	M6021840	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 8 GRATE	EACH	5	5												
*	M6022010	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	25	25												
*	M6024310	VALVE VAULTS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	21													21
*	M6024410	VALVE VAULTS, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	18	1												17
	M6060070	CONCRETE CURB, TYPE B	METER	24.5	24.5												
	M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	19.2	11.7												7.5
*	M6060505	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30 (ABUTTING EXISTING PAVEMENT)	METER	31.5	31.5												
*	M6060510	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30 (DOWELLED)	METER	2,566.6	2566.6												
*	M6060610	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45 (DOWELLED)	METER	53.0	53.0												
	M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	87.9	87.9												
*	M6060705	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60 (ABUTTING EXISTING PAVEMENT)	METER	20.6	20.6												
*	M6060710	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60 (DOWELLED)	METER	11,311.1	11072.8										238.3		
	M6063700	CONCRETE MEDIAN, TYPE M-5	SQ M	632	632												
*	M6064110	CONCRETE MEDIAN, TYPE SB-15.30 (DOWELLED)	SQ M	354	354												
*	M6064210	CONCRETE MEDIAN, TYPE SB-15.60 (DOWELLED)	SQ M	995	995												
*	M6066010	CORRUGATED MEDIAN (DOWELLED)	SQ M	168	168												
*	M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	620	620												
	M7030510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ M	422	422												
	M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	103,564	103,564												
	M7030540	PAVEMENT MARKING TAPE, TYPE III 150MM	METER	1,988	1988												

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS	
NAME	DATE
BDD	9/1/11

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DRAWN BY
CHECKED BY

DATE

11-17-11