

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

### SUMMARY OF QUANTITIES

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%				FEDERAL = 80%				FEDERAL=80%	FEDERAL=80%	FEDERAL = 0%			
					STATE = 20%				STATE = 10%				STATE=0%	STATE=0%	STATE = 0%			
					CITY=0%				CITY = 10%				CITY=20%	CITY=20%	CITY = 100%			
					ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)	ROADWAY (SOMONAUK STREET)
0003	0014	0021		0021				0028	0021	0003	0021	0031	0043					
#	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2													
▪	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1													
▪	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4													
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	32	32													
	67100100	MOBILIZATION	L SUM	1	1													
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	600	600													
*	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	120	120													
	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,993	1,993													
	78200300	PRISMATIC CURB REFLECTOR	EACH	372	372													
	78200410	GUARDRAIL MARKERS, TYPE A	EACH	2	2													
	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2													
▪	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1													
* ▪	80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	20	2		2	2	2	2	2	2	2					
	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	90	41		6	7	7	5	6	5	5	3				
	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	9			1	1	1	1	1	1	1					
	81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	17												17		
▪	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12												12		
▪	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	23												23		
▪	82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1	1													
	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	17	14											3		
	84200804	REMOVAL OF POLE FOUNDATION	EACH	14	14													
▪	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1													
▪	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1													
* ▪	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	19	19													

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS	
NAME	DATE
BDD	9/1/11

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

FILE: \$FILE\$  
 PLOTTED: 9/1/2011

HMC JOB NO. 5122