

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109R)	KENDALL	931	71
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**SIDEWALK REMOVAL SCHEDULE**

LOCATION				SIDEWALK REMOVAL
STATION		STATION	RT/LT	SQ M
<b>IL RTE 47</b>				
18+492.0	TO	18+500.7	LT	18.84
18+515.6	TO	18+625.0	LT	165.52
18+625.0	TO	18+711.8	LT	128.61
18+727.2	TO	18+729.3	RT	5.79
18+735.0	TO	18+800.0	LT	96.84
18+734.1	TO	18+740.4	RT	14.21
18+800.0	TO	18+826.5	LT	38.85
18+798	TO	18+831.7	RT	102.66
18+844.0	TO	18+858.6	LT	22.49
19+356.2	TO	19+365.5	LT	13.68
19+411.5	TO	19+417.2	LT	8.84
19+433.9	TO	19+442.5	LT	35.13
19+624.2	TO	19+636.7	LT	18.08
19+675.0	TO	19+678.0	LT	4.33
19+800.6	TO	19+808.5	RT	20.85
19+818.6	TO	19+824.3	RT	10.15
20+338.7	TO	20+344.1	LT	21.00
20+588.3	TO	20+651.0	RT	80.53
20+714.3	TO	20+716.1	LT	8.89
20+744.6	TO	20+747.6	LT	57.04
20+777.6	TO	20+823.2	RT	138.84
20+787.9	TO	20+810.0	LT	27.29
20+810.3	TO	20+825.7	LT	43.15
20+837.0	TO	20+900.0	LT	180.88
20+837.5	TO	20+900.0	RT	198.58
20+900.0	TO	20+925.2	LT	70.67
20+900.0	TO	20+926.9	RT	81.92
20+939.2	TO	20+999.3	LT	132.79
20+944.4	TO	20+999.4	RT	87.69
20+947.3	TO	20+978.3	RT	37.14
21+188.7	TO	21+214.9	LT	32.80
21+188.7	TO	21+216.0	RT	36.56
21+219.6	TO	21+240.7	LT	23.59
21+221.7	TO	21+354.7	RT	163.82
21+252.2	TO	21+355.6	LT	131.64
21+366.6	TO	21+375.0	LT	27.33
21+375.0	TO	21+473.8	LT	127.16
21+375.0	TO	21+476.7	RT	112.78
21+484.8	TO	21+550.0	LT	88.14
21+550.0	TO	21+590.7	LT	61.41
21+600.2	TO	21+607.2	LT	8.29
21+603.1	TO	21+674.0	LT	156.35
21+686.4	TO	21+725.0	LT	87.64
21+725.0	TO	21+894.0	LT	252.95
21+809.1	TO	21+810.8	LT	18.12
21+861.9	TO	21+863.3	LT	8.65
22+043.0	TO	22+075.0	LT	47.27
22+075.0	TO	22+081.4	LT	8.89
22+217.1	TO	22+224.6	RT	12.10
22+401.7	TO	22+408.0	RT	23.38
22+589.3	TO	22+591.8	LT	2.07
22+979.5	TO	22+984.2	RT	6.83
23+172.5	TO	23+176.5	LT	29.79
23+174.8	TO	23+179.9	RT	20.92
23+208.6	TO	23+212.4	RT	18.41
23+589.0	TO	23+600.0	RT	44.23
23+620.8	TO	23+628.0	RT	35.96
<b>US RTE 34</b>				
189+677.0	TO	189+679.9	RT	7.82
190+341.5	TO	190+345	RT	5.10

LOCATION				SIDEWALK REMOVAL
STATION		STATION	RT/LT	SQ M
<b>ORANGE ST</b>				
1+127.4	TO	1151.6	RT	36.18
<b>WASHINGTON ST</b>				
1+072.8	TO	1+090.5	RT	20.23
1+070.3	TO	1+094.9	LT	28.74
1+104.9	TO	1+118.1	RT	16.90
1+108.6	TO	1+123.5	LT	17.67
1+127.7	TO	1128.8	LT	2.71
<b>FOX ST</b>				
7+911.3	TO	7+955.1	RT	53.80
8+009.9	TO	8+030.0	RT	23.00
8+012.8	TO	8+030.0	LT	26.70
8+030.0	TO	8+040.5	RT	52.67
8+030.0	TO	8+047.3	LT	25.63
<b>VAN EMMON ST</b>				
1+055.6	TO	1+088.6	LT	56.83
1+065.7	TO	1+089.9	RT	76.43
1+110.0	TO	1+137.0	RT	44.13
1+112.2	TO	1+136.4	LT	43.59
<b>RIVER ST</b>				
1+061.3	TO	1+088.9	RT	35.77
<b>MAIN ST NORTH</b>				
1+107.1	TO	1+145.0	LT	64.53
<b>CENTER ST</b>				
1+108.2	TO	1+131.5	LT	28.40
<b>SPRING ST</b>				
1+107.5	TO	1+143.0	RT	41.20
<b>SOMONAUK ST</b>				
1+005.9	TO	1+064.6	LT	69.44
1+057.0	TO	1+064.6	RT	9.08
1+064.6	TO	1+087.5	RT	27.62
1+064.6	TO	1+090.0	LT	31.29
1+111.8	TO	1+134.5	RT	25.81
1+120.6	TO	1+134.5	LT	15.75
1+134.5	TO	1+151.4	RT	21.68
1+134.5	TO	1+215.0	LT	98.40
<b>PARK ST</b>				
1+006.4	TO	1+034.5	LT	32.58
<b>APPLETREE CT</b>				
1+063.9	TO	1+083.8	LT	21.36
1+071.6	TO	1+080.2	RT	9.24
				TOTAL
				4528.64
				ROUNDED
				4529

**LIGHTING REMOVAL SCHEDULE**

LOCATION		REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE		REMOVE EXISTING HANDHOLE	REMOVAL OF POLE FOUNDATION
STATION	RT / LT	STATE OWNED	CITY OWNED	CITY OWNED	STATE OWNED
		EACH	EACH	EACH	EACH
<b>IL 47</b>					
20+864.0	RT			1	
20+866.0	LT		1		
20+868.0	RT			1	
20+894.0	RT		1		
20+894.8	RT			1	
20+921.0	LT		1		
20+926.3	RT			1	
20+961.0	RT	1			1
21+234.0	LT	1			1
22+494.0	RT	1			1
22+562.0	LT	1			1
22+622.0	RT	1			1
22+783.0	LT	1			1
22+833.0	RT	1			1
22+916.0	LT	1			1
<b>US 34</b>					
189+794.0	RT	1			1
189+878.0	LT	1			1
189+923.0	RT	1			1
190+077.0	LT	1			1
190+138.0	RT	1			1
190+206.0	LT	1			1
<b>TOTAL</b>		<b>14</b>	<b>3</b>	<b>4</b>	<b>14</b>

FILE: 064sch\_rem\_47.dgn  
PLOTTED: 8/14/2011

HMG JOB NO. 5122

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>SCHEDULE OF QUANTITIES</b>
DATE		DRAWN BY
		CHECKED BY