

PROPOSED PAVEMENT SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(6CS,13C,108,109)R	KENDALL	931	81
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	AGGREGATE SUBGRADE 300MM	AGGREGATE SUBGRADE 600MM	HOT-MIX ASPHALT BASE COURSE, 115MM	HOT-MIX ASPHALT BASE COURSE WIDENING, 270MM	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 200 MM	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	BITUMINOUS MATERIALS (PRIME COAT)			AGGREGATE (PRIME COAT)	PORTLAND CEMENT CONCRETE PAVEMENT 250 MM (JOINTED)	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	AGGREGATE SHOULDERS, TYPE B 150MM	HOT-MIX ASPHALT SHOULDERS		
											PRIOR TO BASE COURSE	PRIOR TO LEVEL BINDER	PRIOR TO SURFACE COURSE					200MM	250MM	
STATION	STATION	SQ M	SQ M	SQ M	SQ M	SQ M	SQ M	M TON	M TON	M TON	LITER	LITER	LITER	M TON	SQ M	METER	SQ M	SQ M	SQ M	
FAP 326 (IL. 47)																				
WALNUT ST																				
1+010.1 TO	1+035.0	289.6													253.6					
1+035.0 TO	1+040.0	42.0		40.9				23.6		3.7			69.5		14.2	0.07				
LANDMARK AVE																				
1+009.6 TO	1+032.5	623.0													584.5					
ALDI ENTRANCE																				
		78.7		56.7				66.7		21.9			96.4		84.3	0.42			40.1	
COUNTRYSIDE PWY																				
1+091.0 TO	1+165.0	287.9													233.3					
1+165.0 TO	1+184.0			588.5											482.6					
1+009.6 TO	1+032.5			702.6											698.4					
MENARD DR																				
1+009.6 TO	1+032.6	428.6													360.0					
CARPENTER ST																				
1+009.6 TO	1+046.4	715.1													681.4					
TOTALS		95,048.4	54,432.3	2,037.6	782.7	93.9	146.1	975.8	297.6	449.3	250.1	3,673.6	1,145.9	2,661.9	18.77	129,099.3	412.9	114.7	137.7	439.2
ROUNDED		95,048	54,432	2,038	783	94	146	976	298	449	250		7,481		19	129,099	413	115	138	439

FILE: 078sch_prop.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
DATE		SCHEDULE OF QUANTITIES
DRAWN BY		CHECKED BY