

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	100
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE

LOCATION		SIGN	SIZE			SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	WOOD SIGN SUPPORT		TELESCOPING STEEL SIGN SUPPORT	STEEL SIGN SUPPORT, SPECIAL	COMMENTS
STATION	LT/RT		WIDTH	x	DEPTH			SINGLE	DOUBLE			
US 34												
189+705.	RT	R2-1	750	x	900	0.675		4.500			SPEED LIMIT 35	
189+750.	RT	M2-1	750	x	525	0.394		5.025			JCT	
	RT	M1-I100	900	x	900	0.810					ILLINOIS 47	
189+830.	RT	D1-2	1935	x	750		1.451		8.700		ARROW (AHEAD) OSWEGO/ARROW (LT) SUGAR GROVE	
189+885.5	CTR	R6-2	600	x	750	0.450		4.350			ONE WAY RIGHT (IN MEDIAN)	
189+891.0	CTR	R6-2	600	x	750	0.450		4.350			ONE WAY RIGHT (IN MEDIAN)	
189+900.	LT	M3-4	750	x	375	0.281		4.875			WEST	
	LT	M1-I100	900	x	900	0.810					US 34	
189+930.	LT	R2-1	750	x	900	0.675		4.500			SPEED LIMIT 35	
189+965.	RT	M1-I100	900	x	900	0.810		5.025			ILLINOIS 47	
	RT	M6-4	750	x	525	0.394					ARROW (LT & RT)	
189+965.	RT	M1-4	900	x	900	0.810		5.025			US 34	
	RT	M6-3	750	x	525	0.394					ARROW (AHEAD)	
189+971.0	LT	R4-7	600	x	750	0.450			4.45		KEEP RIGHT (SYMBOL)	
190+027.	RT	R4-7	600	x	750	0.450			4.45		KEEP RIGHT (SYMBOL)	
190+035.	LT	M1-I100	900	x	900	0.810		5.025			ILLINOIS 47	
	LT	M6-4	750	x	525	0.394					ARROW (LT & RT)	
190+035.	LT	M1-4	900	x	900	0.810		5.025			US 34	
	LT	M6-3	750	x	525	0.394					ARROW (AHEAD)	
190+065.	CTR	R6-2	600	x	750	0.450		4.350			ONE WAY RIGHT (IN MEDIAN)	
190+070.	RT	R2-1	750	x	900	0.675		4.500			SPEED LIMIT 40	
190+095.	RT	M1-4	900	x	900	0.810		4.875			EAST	
	RT	M3-2	750	x	375	0.281					US 34	
190+100.	CTR	R6-2	600	x	750	0.450		4.350			ONE WAY RIGHT (IN MEDIAN)	
190+113.0	RT	R3-2	600	x	600	0.360		4.200			NO LEFT TURN (IN ISLAND)	
190+156.0	CTR	R6-2	600	x	750	0.450		4.350			ONE WAY RIGHT (IN MEDIAN)	
190+169.0	LT	D1-2	1935	x	750		1.451		8.700		ARROW (LT) YORKVILLE/ARROW (RT) SUGAR GROVE	
190+210.0	LT	R2-1	750	x	900	0.675		4.500			SPEED LIMIT 40	
190+235.	LT	M2-1	750	x	525	0.394		5.025			JCT	
	LT	M1-I100	900	x	900	0.810					ILLINOIS 47	
190+275.	RT	R3-20R	600	x	900	0.540		4.500			BEGIN RIGHT TURN LANE W/45 DEG ARROW	
ELIZABETH ST.												
1+065.0	LT	W14-2	750	x	750	0.563		4.350			NO OUTLET	
MAIN ST. S.												
1+009.0	LT	R1-1	750	x	750	0.563		4.350			STOP	
TOTAL						122.706	23.218	702.925	86.100	64.250	12.925	
TOTAL ROUNDED						122.71	23.22	789.1	64.3	13.0		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
		DRAWN BY
		CHECKED BY
		DATE

FILE: 078sch_prop.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122