

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,10B,109R)	KENDALL	931	122
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE

STR #	UPSTREAM STRUCTURE			DOWNSTREAM STRUCTURE			TRENCH BACKFILL CU M	STORM SEWERS, RUBBER GASKET																			STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1				
	LOCATION			LOCATION				TYPE 1									TYPE 2						TYPE 3									
	STATION	OFFSET		STATION	OFFSET			300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM			1050MM	1200MM	300MM	1200MM
	METER			METER				METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER			METER	METER	METER	METER
249	19+886.000	15.919	LT	251	19+886.500	13.051	LT	1.637																								
250	19+886.500	10.217	LT	251	19+886.500	13.050	LT	1.439																								
251	19+886.500	13.050	LT	255	19+938.000	13.000	LT	109.338						50.149																		
247	19+886.500	13.475	RT	248	19+886.500	10.217	RT																									
248	19+886.500	10.217	RT	250	19+886.500	10.217	LT	18.268																								
254	19+938.000	10.217	LT	255	19+938.000	13.000	LT	1.459																								
255	19+938.000	13.000	LT	260	19+990.000	13.000	LT	150.846						50.649																		
252	19+938.000	17.590	RT	253	19+938.000	10.217	RT	4.609																								
253	19+938.000	10.217	RT	254	19+938.000	10.217	LT	19.240																								
256	19+960.000	17.930	RT	257	19+960.000	10.367	RT	2.314																								
257	19+960.000	10.367	RT	258	19+990.000	10.367	RT	16.672																								
38	19+989.968	20.000	RT	258	19+990.000	10.367	RT	12.194																								
259	19+990.000	10.367	LT	260	19+990.000	13.000	LT	2.228																								
260	19+990.000	13.000	LT	262	20+035.000	12.250	LT	148.889																								
258	19+990.000	10.367	RT	259	19+990.000	10.367	LT	20.923																								
262	20+035.000	12.250	LT	267	20+061.000	13.000	LT	88.993																								
261	20+035.000	17.506	LT	262	20+035.000	12.250	LT																									
265	20+058.000	10.067	LT	266	20+061.000	10.368	LT	0.267	2.213																							
263	20+058.000	10.067	RT	264	20+061.000	10.217	RT	0.287	2.367																							
266	20+061.000	10.367	LT	267	20+061.000	13.000	LT	0.567																								
267	20+061.000	13.000	LT	268	20+092.000	10.810	LT	88.486																								
264	20+061.000	10.217	RT	266	20+061.000	10.367	LT	6.398																								
268	20+092.000	10.810	LT	269	20+175.000	13.350	LT	439.955																								
464	20+104.242	11.382	LT	466	20+138.000	18.000	RT	9.436																								
466	20+138.000	18.000	RT	270	20+175.000	15.700	RT																									
465	20+141.000	31.000	RT	466	20+138.000	18.000	RT																									
273	20+175.000	10.367	LT	269	20+175.000	13.350	LT	3.864																								
269	20+175.000	13.350	LT	276	20+215.000	13.000	LT	240.562																								
270	20+175.000	15.700	RT	271	20+175.000	10.367	RT	12.417																								
271	20+175.000	10.367	RT	273	20+175.000	10.367	LT	54.910																								
275	20+215.000	10.217	LT	276	20+215.000	13.000	LT	1.131																								
276	20+215.000	13.000	LT	278	20+243.000	13.000	LT	168.178																								
274	20+215.000	10.067	RT	275	20+215.000	10.217	LT	5.420	19.647																							
277	20+243.000	10.067	LT	278	20+243.000	13.000	LT	0.350	1.659																							
278	20+243.000	13.000	LT	280	20+270.500	13.000	LT	146.316																								
281	20+255.000	10.067	RT	282	20+271.000	10.217	RT	1.543	15.364																							
279	20+270.500	10.067	LT	280	20+270.500	13.000	LT	0.353	1.659																							
280	20+270.500	13.000	LT	285	20+302.000	12.850	LT	171.875																								
282	20+271.000	10.217	RT	283	20+302.000	10.217	RT	3.225	30.181																							
284	20+302.000	10.217	LT	285	20+302.000	12.851	LT	0.882																								
285	20+302.000	12.850	LT	286	20+328.000	12.850	LT	142.210																								
283	20+302.000	10.217	RT	284	20+302.000	10.217	LT	5.655	19.615																							
287	20+328.000	10.217	LT	286	20+328.000	12.850	LT	0.962																								

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		STORM SEWER SCHEDULE
		DRAWN BY
		CHECKED BY
		DATE

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122