

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(6CS,13C,108,109R)	KENDALL	931	128
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STORM SEWER SCHEDULE

UPSTREAM STRUCTURE		DOWNSTREAM STRUCTURE		TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																						STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1		
STR #	LOCATION		STR #		LOCATION		TYPE 1											TYPE 2						TYPE 3						
	STATION	OFFSET			STATION	OFFSET	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM			1200MM	300MM
	METER			METER		CU M	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER		
578	21+890.500	17.100	LT	580	21+894.500	12.000	LT	1.709																						
580	21+894.500	12.000	LT	585	21+872.500	12.000	LT	98.028																						
583	21+897.980	10.067	LT	580	21+894.500	12.000	LT	2.056	2.862																					
579	21+898.000	10.066	RT	582	21+875.000	10.367	RT	4.026	22.200																					
577	21+936.500	12.000	LT	580	21+894.500	12.000	LT	197.653																						
572	21+937.266	16.507	LT	577	21+936.500	12.000	LT	1.685																						
571	21+937.945	21.000	LT	572	21+937.266	16.507	LT	0.406	3.742																					
573	21+949.094	16.243	LT	572	21+937.266	16.507	LT	2.438	11.029																					
574	21+963.000	10.067	LT	576	21+963.000	14.800	LT	2.706																						
576	21+963.000	14.800	LT	577	21+936.500	12.000	LT	120.185																						
575	21+963.000	10.066	RT	569	21+984.014	10.217	RT	5.129	20.378																					
569	21+984.014	10.217	RT	570	21+987.152	10.366	RT	0.932	2.157																					
564	21+987.152	10.367	LT	562	21+987.152	14.800	LT	8.583																						
562	21+987.152	14.800	LT	576	21+963.000	14.800	LT	112.996																						
568	21+987.152	15.275	RT	570	21+987.152	10.366	RT	1.093	4.107																					
570	21+987.152	10.366	RT	564	21+987.152	10.367	LT	19.758																						
563	21+990.026	10.067	LT	564	21+987.152	10.367	LT	0.227	2.088																					
567	22+015.000	10.217	RT	570	21+987.152	10.366	RT	11.935																						
560	22+023.000	10.067	LT	561	22+023.000	15.000	LT	2.199	3.971																					
561	22+023.000	15.000	LT	562	21+987.152	14.800	LT	159.667																						
566	22+035.000	10.217	RT	567	22+015.000	10.217	RT	4.136	19.181																					
558	22+051.000	10.067	LT	559	22+051.000	15.000	LT	2.123	3.971																					
559	22+051.000	15.000	LT	561	22+023.000	15.000	LT	122.709																						
565	22+055.000	10.067	RT	566	22+035.000	10.217	RT	2.641	19.364																					
556	22+109.000	10.067	LT	557	22+109.000	15.000	LT	1.810	3.971																					
557	22+109.000	15.000	LT	559	22+051.000	15.000	LT	230.105																						
555	22+111.962	16.492	LT	557	22+109.000	15.000	LT	2.355																						
546	22+115.000	10.067	RT	548	22+135.000	10.367	RT	2.931	19.200																					
554	22+135.000	10.067	LT	553	22+135.000	15.000	LT	2.095	3.971																					
553	22+135.000	15.000	LT	557	22+109.000	15.000	LT	86.066																						
547	22+135.000	15.275	RT	548	22+135.000	10.367	RT	1.126	4.106																					
548	22+135.000	10.367	RT	549	22+154.000	10.217	RT	5.983	18.016																					
551	22+153.754	10.067	LT	552	22+156.884	10.517	LT	0.270	2.201																					
549	22+154.000	10.217	RT	550	22+156.884	10.367	RT	0.884	1.904																					
552	22+156.884	10.517	LT	553	22+135.000	15.000	LT	65.202																						
550	22+156.884	10.367	RT	552	22+156.884	10.517	LT	13.816																						
544	22+160.000	16.400	LT	552	22+156.884	10.517	LT	2.464	5.696																					
543	22+185.000	10.517	LT	552	22+156.884	10.517	LT	73.382																						
542	22+185.000	10.067	RT	543	22+185.000	10.517	LT	3.633	19.622																					
541	22+209.000	15.000	LT	543	22+185.000	10.517	LT	66.014																						
540	22+211.000	16.400	LT	541	22+209.000	15.000	LT	1.480																						
539	22+233.000	15.000	LT	541	22+209.000	15.000	LT	66.699																						
531	22+249.000	13.974	RT	532	22+249.000	10.216	RT	3.121																						

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		STORM SEWER SCHEDULE
DATE		DRAWN BY
		CHECKED BY

FILE: 119sch\_ss.dgn  
PLOTTED: 8/14/2011

HMG JOB NO. 5122