CONTRACT NO. 66671

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	130
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																					STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1
									CLASS A																						
									TYPE 1								TYPE 2									TYPE 3					
STR #	LOCATION			STR #	LOCATION				300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM	1200MM	300MM	1200MM
	STATION	OFFSET			STATION	OFFSET																									
		METER				METER		CU M	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER
700	22+547.292	13.905	LT	717	22+589.000	18.800	LT	79.511										40.924													
703	22+551.000	14.817	RT	704	22+575.000	15.567	RT	7.291	23.027																						
705	22+575.000	18.574	RT	704	22+575.000	15.567	RT	0.260	2.205																						
704	22+575.000	15.567	RT	706	22+589.000	15.566	RT	7.385		12.930																					
701	22+584.000	4.068	LT	715	22+589.000	4.368	LT	0.623	4.207																						
717	22+589.000	18.800	LT	720	22+611.500	18.800	LT	60.838											21.548												
716	22+589.000	14.118	LT	717	22+589.000	18.800	LT	8.152										3.795													
715	22+589.000	4.368	LT	716	22+589.000	14.118	LT	7.955										8.863													
706	22+589.000	15.566	RT	715	22+589.000	4.368	LT	15.170										18.864													
720	22+611.500	18.800	LT	722	22+641.000	21.000	LT	73.252											28.446												
719	22+611.500	14.118	LT	720	22+611.500	18.800	LT	2.398	3.698																						
718	22+611.500	4.068	LT	719	22+611.500	14.118	LT	1.544	9.413																						
710	22+625.000	18.275	RT	711	22+625.000	15.566	RT		1.907																						
711	22+625.000	15.566	RT	706	22+589.000	15.566	RT	15.052									34.851														
722	22+641.000	21.000	LT	723	22+664.000	27.100	LT	58.385											22.475												
714	22+642.000	14.837	LT	722	22+641.000	21.000	LT	2.560	4.934																						
713	22+642.000	4.068	LT	714	22+642.000	14.837	LT	1.670	9.967																						
712	22+642.000	15.266	RT	711	22+625.000	15.566	RT	3.500	16.201																						
721	22+645.000	14.826	LT	714	22+642.000	14.837	LT	0.262	2.198																						
845	22+730.698	24.080	LT	773	22+716.493	26.640	LT	31.508												13.050											
844	22+731.086	22.070	LT	845	22+731.000	24.080	LT	0.240	1.028																						
843	22+753.500	23.000	LT	845	22+730.698	24.080	LT													21.628											
841	22+753.500	18.232	LT	843	22+753.500	23.000	LT												3.632												
839	22+753.500	2.067	RT	841	22+753.500	18.232	LT	54.688											19.347												
842	22+726.441	31.800	LT	845	22+730.698	24.080	LT	2.794	7.854																						
837	22+761.400	14.500	RT	839	22+753.500	2.067	RT	37.815											13.595												
838	22+762.630	12.258	RT	839	22+761.400	14.500	RT	0.346	1.596																						
836	22+774.900	14.500	RT	837	22+761.400	14.500	RT												12.364												
EX	22+775.480	16.051	RT	836	22+774.900	14.500	RT										0.854														
818	22+790.500	21.000	LT	843	22+753.500	23.000	LT	66.794											35.918												
817	22+790.500	17.853	LT	818	22+790.500	21.000	LT		2.345																						
835	22+792.000	14.500	RT	836	22+774.900	14.500	RT											16.030													
834	22+792.000	11.816	RT	835	22+792.000	14.500	RT		1.700																						
833	22+792.000	1.766	RT	834	22+792.000	11.816	RT	1.082	9.413																						
816	22+804.000	21.000	LT	818	22+790.500	21.000	LT												12.548												
815	22+804.000	17.568	LT	816	22+804.000	21.000	LT		2.630																						
832	22+833.000	14.500	RT	835	22+792.000	14.500	RT	40.837										39.930													
848	22+833.000	11.816	RT	832	22+833.000	14.500	RT		1.700																						
847	22+833.000	1.916	RT	848	22+833.000	11.816	RT	2.071	9.081																						
814	22+835.000	20.875	LT	816	22+804.000	21.000	LT	15.265										29.930													
831	22+835.000	17.568	LT	814	22+835.000	20.875	LT		2.505																						
846	22+839.500	1.766	RT	847	22+833.000	1.916	RT	0.946	5.865																						

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011