

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	131
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STORM SEWER SCHEDULE

STR #	UPSTREAM STRUCTURE			DOWNSTREAM STRUCTURE			TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																				STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1	
	LOCATION		STR #	LOCATION		CU M		TYPE 1										TYPE 2						TYPE 3						
	STATION	OFFSET		STATION	OFFSET			300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM			1200MM
	METER		METER		METER	METER		METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER			METER
813	22+859.000	20.558	LT	814	22+835.000	20.875	LT																							
830	22+859.000	17.250	LT	813	22+859.000	20.558	LT	2.506																						
829	22+860.000	15.250	RT	832	22+833.000	14.500	RT	16.756																						
828	22+860.000	12.479	RT	829	22+860.000	15.250	RT	1.969																						
812	22+881.000	20.061	LT	813	22+859.000	20.558	LT		20.935																					
824	22+881.145	16.907	LT	812	22+881.000	20.060	LT	2.172																						
823	22+884.154	16.679	LT	824	22+881.145	16.907	LT	0.292	2.381																					
827	22+888.500	16.000	RT	829	22+860.000	15.250	RT																							
826	22+888.593	13.982	RT	827	22+888.500	16.000	RT	1.036																						
825	22+891.585	13.987	RT	826	22+888.593	13.982	RT	0.288	2.355																					
811	22+915.000	15.744	LT	812	22+881.000	20.061	LT	0.991	33.471																					
822	22+915.000	16.474	RT	827	22+888.500	16.000	RT	25.355																						
821	22+915.000	13.766	RT	822	22+915.000	16.474	RT	1.906																						
820	22+935.000	16.674	RT	822	22+915.000	16.474	RT	19.199																						
919	22+974.000	13.202	RT	918	22+981.100	13.000	RT	1.097	5.828																					
917	22+980.926	17.334	RT	918	22+981.100	13.000	RT	7.336																						
918	22+981.100	13.000	RT	923	22+982.000	17.000	LT	86.849																						
923	22+982.000	17.000	LT	924	22+982.717	24.000	LT	14.078																						
921	23+013.264	14.553	LT	922	23+013.264	16.400	LT	0.863																						
922	23+013.264	16.400	LT	923	22+982.000	17.008	LT																							
920	23+016.264	14.317	LT	921	23+013.264	14.553	LT	0.291	2.373																					
916	23+016.511	12.500	RT	918	22+981.100	13.000	RT																							
915	23+016.511	10.217	RT	916	23+016.511	12.500	RT	1.139																						
914	23+019.508	10.066	RT	915	23+016.511	10.217	RT	0.289	2.364																					
909	23+062.000	13.011	LT	910	23+062.000	15.351	LT	0.222	1.538																					
910	23+062.000	15.351	LT	922	23+013.264	16.400	LT	103.344																						
911	23+062.000	12.500	RT	916	23+016.511	12.500	RT																							
912	23+062.000	10.066	RT	911	23+062.000	12.500	RT	1.472																						
904	23+095.000	12.068	LT	914	23+095.000	14.500	LT	1.470																						
905	23+095.000	14.500	LT	910	23+062.000	15.351	LT	46.688																						
906	23+105.000	16.674	RT	907	23+105.000	12.500	RT																							
907	23+105.000	12.500	RT	911	23+062.000	12.500	RT																							
908	23+105.000	10.066	RT	907	23+105.000	12.500	RT	1.472																						
903	23+135.000	12.500	RT	907	23+105.000	12.500	RT																							
902	23+135.000	10.066	RT	903	23+135.000	12.500	RT	1.472																						
901	23+135.003	11.075	LT	905	23+095.000	14.500	LT	21.752																						
898	23+165.000	12.000	LT	901	23+135.003	11.075	LT	22.426																						
897	23+174.517	17.531	LT	898	23+165.000	12.000	LT	10.244																						
899	23+176.000	16.013	RT	900	23+176.000	12.500	RT	0.518	2.551																					
900	23+176.000	12.500	RT	903	23+135.000	12.500	RT	22.228																						
896	23+177.886	23.961	LT	897	23+174.517	17.531	LT	2.801	6.440																					
895	23+205.497	26.555	LT	896	23+177.886	23.961	LT	7.523	26.913																					

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">STORM SEWER SCHEDULE</p> <p align="right">DRAWN BY _____ CHECKED BY _____</p> <p>DATE _____</p>

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122