

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109)R	KENDALL	931	133
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

STR #	UPSTREAM STRUCTURE		DOWNSTREAM STRUCTURE		TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																				STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1			
	LOCATION		LOCATION			TYPE 1										TYPE 2						TYPE 3								
	STATION	OFFSET	STATION	OFFSET		300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM			1200MM	300MM	1200MM
	METER	METER	METER	METER		METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER			METER	METER	METER
IL 126																														
462	50+024.077	12.210	LT	464	50+027.202	11.382	LT	0.276	2.271																					
460	50+024.471	10.927	RT	461	50+027.000	10.124	RT	0.230	1.852																					
461	50+027.000	10.124	RT	464	50+027.202	11.382	LT	12.942					20.198																	
459	50+065.000	12.574	LT	464	50+027.202	11.382	LT	11.815						36.578																
457	50+065.000	8.217	LT	459	50+065.000	12.574	LT						3.373																	
455	50+065.000	9.200	RT	461	50+027.000	10.124	RT	36.862																						
456	50+065.000	6.508	RT	455	50+065.000	9.200	RT	1.890																						
454	50+086.237	9.152	RT	455	50+065.000	9.200	RT	20.435																						
453	50+125.000	12.573	LT	459	50+065.000	12.574	LT	58.930																						
451	50+125.000	8.217	LT	453	50+125.000	12.573	LT						3.372																	
450	50+169.780	12.460	LT	453	50+125.000	12.573	LT	43.893																						
US 34																														
808	189+215.139	12.675	LT	809	189+210.500	12.675	LT					4.097																		
807	189+253.800	11.628	LT	808	189+215.139	12.675	LT																							
806	189+290.000	12.313	LT	807	189+253.800	11.628	LT																							
805	189+324.913	12.843	LT	806	189+290.000	12.313	LT																							
EX	189+326.256	11.217	LT	805	189+324.913	12.843	LT							1.852																
804	189+375.000	12.841	LT	805	189+324.913	12.843	LT																							
803	189+420.000	12.884	LT	804	189+375.000	12.841	LT																							
802	189+502.093	13.068	LT	803	189+420.000	12.884	LT	129.734																						
801	189+555.750	13.263	LT	802	189+502.093	13.068	LT	74.695																						
800	189+622.000	13.291	LT	801	189+555.750	13.263	LT	76.218																						
799	189+666.500	12.200	LT	800	189+622.000	13.291	LT	201.268																						
797	189+722.000	12.216	LT	799	189+666.500	12.200	LT	366.634																						
796	189+722.000	8.068	RT	797	189+722.000	12.216	LT	4.412	19.322																					
798	189+752.500	12.788	LT	795	189+755.500	12.404	LT	0.251	2.063																					
790	189+752.500	8.312	RT	791	189+755.500	8.679	RT	0.273	2.220																					
792	189+755.500	18.974	LT	795	189+755.500	12.404	LT	3.350	5.608																					
795	189+755.500	12.404	LT	797	189+722.000	12.216	LT	190.683																						
794	189+755.500	0.305	LT	795	189+755.500	12.404	LT	9.266						10.955																
789	189+755.500	14.695	RT	791	189+755.500	8.679	RT	1.838						5.214																
791	189+755.500	8.679	RT	794	189+755.500	0.305	LT	5.695						8.000																
793	189+765.000	14.474	LT	795	189+755.500	12.404	LT	55.430							8.920															
787	189+844.979	15.293	LT	793	189+765.000	14.474	LT	474.482							79.180															
785	189+845.000	4.406	LT	787	189+844.979	15.293	LT	5.259						9.578																
783	189+845.000	14.118	RT	785	189+845.000	4.406	LT	6.092						17.540																
786	189+847.988	14.910	LT	787	189+844.979	15.293	LT	0.261	2.134																					
782	189+848.000	13.968	RT	783	189+845.000	14.118	RT	0.288	2.367																					

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">STORM SEWER SCHEDULE</p> <p align="right">DRAWN BY _____ CHECKED BY _____</p> <p>DATE _____</p>

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122