STORM SEWER SCHEDULE

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																						STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1
									CLASS A																							
									TYPE 1								TYPE 2									TYPE 3				
STR #	LOCATION			STR #	LOCATION				300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM	1200MM	300MM	1200MM
	STATION	OFFSET			STATION	OFFSET																										
		METER				METER		CU M	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER
749	190+176.750	15.652	LT	750	190+133.000	15.800	LT	95.277											42.799													
746	190+176.750	1.298	LT	749	190+176.750	15.652	LT	6.320									13.370															
745	190+176.750	10.262	RT	746	190+176.750	1.298	LT	2.220	10.923																							
747	190+188.000	17.000	LT	749	190+176.750	15.652	LT	10.214											10.379													
744	190+227.000	15.874	LT	747	190+188.000	17.000	LT												38.065													
743	190+227.000	13.616	LT	744	190+227.000	15.874	LT		1.274																							
740	190+227.000	4.798	LT	743	190+227.000	13.616	LT	0.861	8.181																							
742	190+259.000	15.874	LT	744	190+227.000	15.874	LT												31.048													
741	190+259.000	13.616	LT	742	190+259.000	15.874	LT		1.274																							
739	190+259.000	8.435	RT	741	190+259.000	13.616	LT	5.846	21.414																							
738	190+286.000	15.700	LT	742	190+259.000	15.874	LT			25.930																						
737	190+286.000	13.616	LT	738	190+286.000	15.699	LT										1.099															
736	190+286.000	8.068	RT	737	190+286.000	13.616	LT	4.923	21.047																							
730	190+302.000	8.068	RT	731	190+305.000	8.218	RT	0.205	2.367																							
735	190+305.000	15.700	LT	738	190+286.000	15.700	LT			17.930																						
734	190+305.000	13.766	LT	735	190+305.000	15.700	LT		0.785																							
731	190+305.000	8.218	RT	734	190+305.000	13.766	LT	2.825	21.000																							
733	190+308.000	13.466	LT	734	190+305.000	13.766	LT	0.270	2.213																							
ELIZABETH ST.																																
425	1+083.641	4.343	RT	426	1+082.610	12.585	RT										7.487															
426	1+082.610	12.585	RT	427	1+069.025	8.244	RT	0.575	13.443																							
427	1+069.025	8.244	RT	428	1+061.677	4.231	RT		7.553																							
428	1+061.677	4.231	RT	429	1+061.677	3.952	LT	3.029	7.364																							
429	1+061.677	3.952	LT	430	1+064.545	13.738	LT		7.959																							
SOUTH MAIN ST.																																
431	1+020.000	4.067	RT	432	1+020.000	4.217	LT	1.284	7.647																							
432	1+020.000	4.217	LT	433	1+012.777	11.061	LT										7.712															
FOX ST.																																
331	7+929.090	6.687	LT	334	7+930.000	5.168	LT		1.134																							
334	7+930.000	5.168	LT	335	7+951.000	5.635	LT	6.272	19.861																							
332	7+945.984	5.875	RT	333	7+951.000	4.735	RT	7.820											4.008													
333	7+951.000	4.735	RT	335	7+951.000	5.635	LT	10.595											9.050													
335	7+951.000	5.635	LT	337	7+969.975	7.309	LT	19.642											17.913													
336	7+969.330	11.880	LT	337	7+969.975	7.309	LT	0.920	3.632																							

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011