CONTRACT NO. 66671

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	136
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																				STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1
									CLASS A																					
									TYPE 1								TYPE 2									TYPE 3				
STR #	LOCATION STATION	LOCATION OFFSET		STR #	LOCATION STATION	LOCATION OFFSET			300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM	1200MM	300MM	1200MM
		METER				METER		CU M	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER
337	7+969.975	7.309	LT	338	7+981.905	9.237	LT	11.189											11.133												
330	8+057.718	5.185	RT																												
VAN EMMON ST.																															
370	1+022.500	3.835	LT	368	1+042.000	2.000	LT	5.107	18.784																						
369	1+042.000	3.835	LT	368	1+042.000	2.000	LT	0.188	1.033																						
368	1+042.000	2.000	LT	366	1+062.234	2.000	LT	8.947	19.085																						
367	1+062.234	6.835	LT	366	1+062.234	2.000	LT	0.789	4.033																						
366	1+062.234	2.000	LT	364	1+082.000	2.000	LT	9.144	18.617																						
365	1+082.000	3.835	LT	364	1+082.000	2.000	LT	0.115	0.851																						
364	1+082.000	2.000	LT	363	1+088.572	3.500	LT	3.684										5.854													
363	1+088.572	3.500	LT	362	1+090.558	11.509	LT	3.899										7.365													
SOMONAUK ST.																															
445	1+018.500	4.767	RT	444	1+018.500	3.426	LT	1.084	7.391																						
444	1+018.500	3.426	LT	443	1+028.000	5.384	LT	1.869		8.630																					
443	1+028.000	5.384	LT	440	1+068.000	7.500	LT	18.413										38.986													
442	1+068.000	5.817	RT	441	1+068.000	5.728	LT	2.132	10.908																						
441	1+068.000	5.728	LT	440	1+068.000	7.500	LT	0.350									0.788														
440	1+068.000	7.500	LT	606	1+081.493	5.644	LT	7.193										12.550													
WALNUT ST.																															
435	22+210.518	31.437	RT	436	22+217.622	29.216	RT	0.877	6.806																						
436	22+217.622	29.216	RT	437	22+221.651	42.223	RT	2.480																						12.798	
437	22+221.651	42.223	RT																												
CARPENTER ST.																															
850	23+597.416	17.466	RT	851	23+603.171	27.460	RT	1.425	10.896																						
851	23+603.171	27.460	RT	853	23+617.143	28.925	RT	2.997	13.229																						
853	23+617.143	28.925	RT	854	23+620.000	29.000	RT	0.750									1.874														
854	23+620.000	29.000	RT	EX	23+619.868	32.008	RT										1.861														
852	23+623.467	17.294	RT	854	23+620.000	29.000	RT	3.052	11.407																						
							TOTALS	18,566.9	2,733.9	442.1	142.7	190.3	59.1	137.0	68.0	242.9	1,254.8	829.9	634.2	514.4	858.4	965.3	810.0	185.0	426.6	193.0	14.9	54.5	424.4	12.8	79.8
							USE	18567	2734.0	442.0	142.5	190.5	59.0	137.0	68.0	243.0	1255.0	830.0	634.0	514.5	858.5	965.5	810.0	185.0	426.5	193.0	15.0	54.5	424.5	13.0	80.0

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/22/2011