CONTRACT NO. 66671

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	138
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				MANHOLES, TYPE A																				INLETS										
								1.2 M DIAMETER						1.5 M DIAMETER					1.8 M DIAMETER			2.1 M DIAMETER		2.4 M DIAMETER					2.7 M DIAMETER		TYPE A				TYPE B						
STR #	LOCATION			STR #	LOCATION			TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G	TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 1 FRAME, CLOSED LID	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 1 FRAME, CLOSED LID	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	SPECIAL	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 3V F&G	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G	TYPE 1 FRAME, CLOSED LID	TYPE 1 FRAME, OPEN LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G
	STATION	OFFSET METER			STATION	OFFSET METER		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
168	18+965.000	13.500 RT		170	19+025.000	13.500 RT								1																												
167	18+965.000	10.217 RT		168	18+965.000	13.500 RT																																1				
19	18+995.000	14.250 LT		171	19+006.472	13.204 LT																																				
171	19+006.472	13.204 LT		172	19+011.000	12.500 LT																																1				
172	19+011.000	12.500 LT		173	19+053.000	12.500 LT				1																																
23	19+011.000	19.000 LT		172	19+011.000	12.500 LT																																				
170	19+025.000	13.500 RT		178	19+085.500	13.500 RT								1																												
169	19+025.000	10.217 RT		170	19+025.000	13.500 RT																																1				
175	19+053.000	10.067 LT		173	19+053.000	12.500 LT																														1						
173	19+053.000	12.500 LT		174	19+085.000	12.500 LT		1																																		
176	19+085.000	10.217 LT		177	19+085.000	10.217 RT																																1				
174	19+085.000	12.500 LT		176	19+085.000	10.217 LT		1																																		
177	19+085.000	10.217 RT		178	19+085.500	13.500 RT																																1				
178	19+085.500	13.500 RT		181	19+145.000	13.350 RT																1																				
24	19+088.000	19.165 RT		178	19+085.500	13.500 RT																										1										
179	19+145.000	10.067 LT		180	19+145.000	10.217 RT																														1						
181	19+145.000	13.350 RT		184	19+205.000	13.350 RT																	1																		
180	19+145.000	10.217 RT		181	19+145.000	13.350 RT																																1				
182	19+205.000	10.067 LT		183	19+205.000	10.217 RT																														1						
184	19+205.000	13.350 RT		187	19+265.000	13.500 RT																	1																		
183	19+205.000	10.217 RT		184	19+205.000	13.350 RT																																1				
185	19+265.000	10.067 LT		186	19+265.000	10.217 RT																														1						
187	19+265.000	13.500 RT		190	19+318.000	13.500 RT														1																					
186	19+265.000	10.217 RT		187	19+265.000	13.500 RT																																1				
188	19+318.000	10.067 LT		189	19+318.000	10.217 RT																														1						
190	19+318.000	13.500 RT		191	19+345.000	13.500 RT														1																					
189	19+318.000	10.217 RT		190	19+318.000	13.500 RT																																1				
191	19+345.000	13.500 RT		192	19+385.000	13.500 RT																	1																		
194	19+385.000	10.367 LT		193	19+385.000	10.217 RT		1																																		
196	19+385.000	14.657 LT		194	19+385.000	10.367 LT																														1						
192	19+385.000	13.500 RT		198	19+442.000	13.500 RT														1																					
193	19+385.000	10.217 RT		192	19+385.000	13.500 RT																																1				
195	19+414.359	17.713 LT		194	19+385.000	10.367 LT																														1						
198	19+442.000	13.500 RT		202	19+475.000	13.500 RT														1																					
197	19+442.000	10.217 RT		198	19+442.000	13.500 RT																																1				
200	19+475.000	10.217 LT		201	19+475.000	10.217 RT																																1				
202	19+475.000	13.500 RT		206	19+515.000	13.500 RT														1																					
201	19+475.000	10.217 RT		202	19+475.000	13.500 RT																																1				
199	19+475.006	13.957 LT		200	19+475.000	10.217 LT																														1						
204	19+515.000	10.217 LT		205	19+515.000	10.217 RT																																1				
206	19+515.000	13.500 RT		210	19+584.000	14.125 RT														1																					
205	19+515.000	10.217 RT		206	19+515.000	13.500 RT																																1				
203	19+515.005	14.708 LT		204	19+515.000	10.217 LT																														1						

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011