

**CLASS B PATCHING 17" SCHEDULE  
I-80**

LOCATION (MILE MARKERS)*	DIRECTION (WB/EB)	LENGTH	CL B PATCH TY II SQ YD		CL B PATCH TY III SQ YD		CL B PATCH TY IV SQ YD		DOWEL BARS 1 1/2" EACH	SAW CUTS FOOT	PAVEMENT FABRIC SQ YD	TIE BARS 3/4" EACH PL
			PL	DL	PL	DL	PL	DL				
56.02	EB	6		8					20	48		
56.50	WB	20					27		20	76	27	20
56.59	EB	6	8						20	48		
57.20	WB	6		8					20	48		
57.45	EB	12			16				20	60		
57.90	WB	8		11					20	52		
<b>URBAN TOTAL</b>			8	27	16	0	0	27	120	332	27	20
58.20	EB	8		11					20	52		
58.35	WB	12			16				20	60		
58.45	EB	8	11						20	52		
59.20	WB	8		11					20	52		
59.45	EB	8	11						20	52		
59.65	WB	12			16				20	60		
60.20	EB	8		11					20	52		
60.30	WB	8	11						20	52		
60.45	EB	20					27		20	76	27	20
60.75	WB	8	11						20	52		
61.20	EB	8	11						20	52		
61.80	WB	8	11						20	52		
<b>RURAL TOTALS</b>			66	33	16	16	27	0	240	664	27	20
<b>GRAND TOTALS</b>				134		48		54	380	996	54	40

\* CONTINGENCY QUANTITY-ACTUAL LOCATIONS WILL VARY  
 \*\*URBAN/RURAL SPLIT IS AS FOLLOWS: URBAN 1080+00 TO STA 1205+10.17 -RURAL STA 1205+10.17 TO STA 1405+64

**SURFACE REMOVAL-PCC AND HMA**

LOCATION	LENGTH FT	HMA SURF REM VAR. DEPTH* SQ YD	PCC SURF REM- BJ SQ YD	HMA SURF REM- BJ SQ YD
1079+30 TO 1080+00	70.0			296.0
SN 006-0131	200.0	844.0		
SN 006-0038	240.0	1013.0		
1405+64 TO 1406+34	70.0			296.0
<b>WESTBOUND</b>				
1079+30 TO 1080+00	70.0			296.0
SN 006-0131	200.0	844.0		
SN 006-0038	240.0	1013.0		
1405+64 TO 1406+34	70.0			296.0
<b>RT 26 NW RAMP</b>				
1132+27 TO 1131+57	70.0			226.0
<b>RT 26 SW RAMP</b>				
1127+74 TO 1127+04	70.0			226.0
<b>RT 26 NE RAMP</b>				
1134+43 TO 1134+13	70.0			226.0
<b>RT 26 SE RAMP</b>				
1135+36 TO 1136+06	70.0			226.0
<b>I 180 NW RAMP</b>				
1379+30 TO 1380+00	70.0			226.0
<b>I 180 SW RAMP</b>				
1360+30 TO 1361+00	70.0			226.0
<b>I 180 NE RAMP</b>				
1193+75 TO 1394+45	70.0			226.0
<b>I 180 SE RAMP</b>				
1381+40 TO 1382+10	70.0			226.0
<b>MEDIAN</b>				
WEST X-OVER			1700.0	
EAST X-OVER			1700.0	
<b>URBAN TOTALS</b>		0.0	1700.0	1496.0
<b>RURAL TOTALS</b>		3714.0	1700.0	1496.0
<b>GRAND TOTAL</b>		3714.0	3400.0	2992.0

\* UNDER STRUCTURES TO MAINTAIN EXISTING CLEARANCES  
 \*\*URBAN/RURAL SPLIT IS AS FOLLOWS: URBAN 1080+00 TO STA 1205+10.17 -RURAL STA 1205+10.17 TO STA 1405+64

MAINTENANCE CROSSOVER AND OVERLAY	
STATION	HMA SURF - 1 3/4" CSE CLASS C TON
1098+00	21.50
1166+00	17.99
<b>URBAN TOTAL</b>	<b>40.00</b>