

SUMMARY OF QUANTITIES					
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE	0005	0040
			80% FED. 20% STATE	RURAL	RURAL PROPOSED SN 053-2578 EXISTING SN 053-2541
			TOTAL QUANTITY	ROADWAY	
20200100	EARTH EXCAVATION	CU YD	139	139	
20400800	FURNISHED EXCAVATION	CU YD	131	131	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	67		67
25000210	SEEDING, CLASS 2A	ACRE	0.52	0.52	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	47	47	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	47	47	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	47	47	
25100115	MULCH, METHOD 2	ACRE	0.52	0.52	
25100630	EROSION CONTROL BLANKET	SQ YD	44	44	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	31	31	
28000305	TEMPORARY DITCH CHECKS	FOOT	14	14	
28000400	PERIMETER EROSION BARRIER	FOOT	40	40	
28100107	STONE RIPRAP, CLASS A4	SQ YD	32	32	
28200200	FILTER FABRIC	SQ YD	32	32	
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	118	118	
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	610	610	
35501336	HOT-MIX ASPHALT BASE COURSE, 13"	SQ YD	96	96	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	109	109	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.5	0.5	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	0.7	0.7	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	56	56	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	408	408	
40600990	TEMPORARY RAMP	SQ YD	480	480	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	113	113	
44000100	PAVEMENT REMOVAL	SQ YD	383	383	
44004250	PAVED SHOULDER REMOVAL	SQ YD	231	231	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	159	159	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
54001061	GRADED BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2		2
54011003	PRECAST CONCRETE BOX CULVERTS 10' X 3'	FOOT	41		41