



Minimum Section Modulus = 2.0 in.<sup>3</sup>/ft.

**TEMPORARY SHEET PILING**

If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.

ITEM	UNIT	TOTAL
Temporary Sheet Piling	SQ FT	194



Signed: *Olufemi A. Oladeinde* 08/23/2011  
 OLUFEMI A. OLADEINDE, P.E., S.E. Date  
 LICENSE EXPIRES 11-30-2012



DESIGNED - AG	EXAMINED	DATE
CHECKED - OAO	PASSED	
DRAWN - TCS		
CHECKED - AG		

ENGINEER OF BRIDGE DESIGN	
ENGINEER OF BRIDGES AND STRUCTURES	

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

TEMPORARY SHEET PILING  
 SHEET NO. OF SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(1211)	LIVINGSTON	27	15
			CONTRACT NO. 66869	
ILLINOIS FED. AID PROJECT				