

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	RURAL TOTAL QUALITY	CONSTRUCTION TYPE CODE:		
				0004	0011	0011
				ROADWAY	SN 038-0222 (SB I-57)	SN 038-0223 (NB I-57)
20200100	EARTH EXCAVATION	CU YD	1190	1190		
20300100	CHANNEL EXCAVATION	CU YD	6439	6439		
20400800	FURNISHED EXCAVATION	CU YD	2320	2320		
* 25000300	SEEDING, CLASS 3	ACRE	1.4	1.4		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	123	123		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	123	123		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	123	123		
25100630	EROSION CONTROL BLANKET	SQ YD	7431	7431		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	4264	4264		
28000305	TEMPORARY DITCH CHECKS	FOOT	54	54		
28000400	PERIMETER EROSION BARRIER	FOOT	2020	2020		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28100107	STONE RIPRAP, CLASS A4	SQ YD	2993	149	1,659	1,185
28200200	FILTER FABRIC	SQ YD	3134	290	1,659	1,185
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2243	2243		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	154	154		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	910	910		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	386	386		
42001300	PROTECTIVE COAT	SQ YD	176	176		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	176	176		
42100615	PAVEMENT REINFORCEMENT	SQ YD	176	176		
44000100	PAVEMENT REMOVAL	SQ YD	492	492		
44004250	PAVED SHOULDER REMOVAL	SQ YD	4262	4262		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	69	69		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1435	1435		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		1	1

CODE NUMBER	ITEM	UNIT	RURAL TOTAL QUALITY	CONSTRUCTION TYPE CODE:		
				0004	0011	0011
				ROADWAY	SN 038-0222 (SB I-57)	SN 038-0223 (NB I-57)
50200100	STRUCTURE EXCAVATION	CU YD	472		236	236
50300100	FLOOR DRAINS	EACH	20		10	10
50300225	CONCRETE STRUCTURES	CU YD	305.4		152.7	152.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	629.8		314.9	314.9
50300260	BRIDGE DECK GROOVING	SQ YD	1488		744	744
50300280	CONCRETE ENCASEMENT	CU YD	19.6		9.8	9.8
50300300	PROTECTIVE COAT	SQ YD	1860		930	930
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5
50500505	STUD SHEAR CONNECTORS	EACH	10320		5,160	5,160
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	188780		94,390	94,390
50800515	BAR SPLICERS	EACH	1656		828	828
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1347		664	683
51202305	DRIVING PILES	FOOT	1347		664	683
51203600	TEST PILE STEEL HP12X53	EACH	6		3	3
51204650	PILE SHOES	EACH	56		28	28
51500100	NAME PLATES	EACH	2		1	1
52100520	ANCHOR BOLTS, 1"	EACH	96		48	48
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	154		77	77
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	8	8		
60100905	PIPE DRAINS 4"	FOOT	32	32		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	800	800		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	1033	1033		
63500105	DELINEATORS	EACH	4	4		
64200105	SHOULDER RUMBLE STRIPS	FOOT	3456	3456		
66500105	WOVEN WIRE FENCE, 4'	FOOT	280	280		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		

* SPECIALTY ITEM

