

SCHEDULE OF QUANTITIES

GUARDRAIL							
LOCATION		GUARDRAIL REMOVAL	SPBGR TYPE A 6 FT POSTS	TBT TYPE 6	TBT TYPE 1, SPECIAL (FLARED)	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER-DIRECT APPLIED
		FOOT	FOOT	EACH	EACH	EACH	EACH
RIGHT SIDE							
STA. 1358+05	TO STA. 1360+07	202					
STA. 1354+61	TO STA. 1357+00	239					
STA. 1354+61	TO STA. 1356+36		175	1			
STA. 1358+68	TO STA. 1360+43		175	1			
STA. 1354+11	TO STA. 1356+79				1	4	1
STA. 1358+25	TO STA. 1360+93				1	4	1
LEFT SIDE							
STA. 1358+05	TO STA. 1361+96	392					
STA. 1355+00	TO STA. 1357+00	200					
STA. 1354+11	TO STA. 1356+36		225	1			
STA. 1358+68	TO STA. 1360+93		225	1			
STA. 1353+61	TO STA. 1356+79				1	4	1
STA. 1358+25	TO STA. 1361+43				1	4	1
TOTAL:		1033	800	4	4	16	4

TEMPORARY EROSION CONTROL						
TEMPORARY DITCH CHECKS			PERIMETER EROSION BARRIER			
STATION	OFFSET	LENGTH (FT)	STATION	STATION	RT/LT	FOOT
STA. 1352+93	1.0 LT	6	STA. 1352+20	TO STA. 1357+00	RT	480
STA. 1353+93	1.0 LT	6	STA. 1357+50	TO STA. 1362+80	LT	530
STA. 1354+93	1.6 LT	6	STA. 1352+20	TO STA. 1357+00	RT	480
STA. 1355+93	3.4 LT	6	STA. 1357+50	TO STA. 1362+80	LT	530
STA. 1358+94	1.4 LT	6				
STA. 1359+92	1.3 LT	6				
STA. 1360+92	1.3 LT	5				
STA. 1361+92	1.3 LT	6				
STA. 1362+92	1.3 LT	7				
TOTAL:		54	TOTAL:			2020

EARTHWORK						
LOCATION		EARTH EXCAVATION (2)	EARTH EX. ADJ. FOR SHRINKAGE (1)	FURNISHED EXCAVATION (3)	EARTHWORK BAL. WASTE (+) OR SHORTAGE (-)	
		CU YD	CU YD	CU YD	CU YD	
STA. 1352+20	TO STA. 1353+00	140	105	269	(164)	
STA. 1353+00	TO STA. 1354+00	106	80	189	(109)	
STA. 1354+00	TO STA. 1355+00	119	89	229	(140)	
STA. 1355+00	TO STA. 1356+00	135	101	263	(162)	
STA. 1356+00	TO STA. 1356+64	190	143	580	(437)	
STA. 1358+40	TO STA. 1359+00	157	118	257	(139)	
STA. 1359+00	TO STA. 1360+00	163	122	257	(135)	
STA. 1360+00	TO STA. 1361+00	60	45	91	(46)	
STA. 1361+00	TO STA. 1362+00	38	29	62	(33)	
STA. 1362+00	TO STA. 1362+80	82	62	123	(61)	
TOTAL:		1190	894	2320	(1426)	

- (1) QUANTITY OF EARTH EXCAVATION ADJUSTED FOR A SHRINKAGE FACTOR OF 25% .
 (2) ACCOUNTS FOR TOP 6 INCHES OF UNSUITABLE SOIL INCLUDED IN EARTH EXCAVATION.
 (3) INCLUDES 6 INCHES OF UNSUITABLE SOIL REMOVAL.

TEMPORARY PAVEMENT MARKINGS							
LOCATION	STATION		LENGTH	TEMPORARY PAVEMENT MARKING -LINE WHITE 4"	TEMPORARY PAVEMENT MARKING -LINE YELLOW 4"	SHORT TERM PAVEMENT MARKING	WORK ZONE, PAVEMENT MARKING REMOVAL
				FOOT	FOOT	FOOT	SQ FT
NORTHBOUND	STA. 1349+60	TO STA. 1352+20	260	260	260		173
	STA. 1352+20	TO STA. 1363+80	1160	1160	1160	5300	3541
SOUTHBOUND	STA. 1363+80	TO STA. 1367+25	345	345	345		230
	STA. 1347+75	TO STA. 1351+20	345	345	345		230
NORTHBOUND	STA. 1351+20	TO STA. 1362+80	1160	1160	1160	5300	3541
	STA. 1362+80	TO STA. 1365+40	260	260	260		173
SOUTHBOUND	STA. 1349+60	TO STA. 1352+20	260	260	260		173
	STA. 1352+20	TO STA. 1363+80	1160	1160	1160		297
SOUTHBOUND	STA. 1363+80	TO STA. 1367+25	345	345	345		0
	STA. 1347+75	TO STA. 1351+20	345	345	345		297
SOUTHBOUND	STA. 1351+20	TO STA. 1362+80	1160	1160	1160		173
	STA. 1362+80	TO STA. 1365+40	260	260	260		0
TOTAL:				7060	7060	10600	8828

