

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	URBAN		801.FED./201.STATE	
				CONSTRUCTION TYPE CODES			
				ROADWAY 0004	EX SN 019-0013 PR SN 019-0048 0011		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	175	175			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	118	118			
20101000	TEMPORARY FENCE	FOOT	200	200			
20200100	EARTH EXCAVATION	CU YD	1,370	1,370			
20400800	FURNISHED EXCAVATION	CU YD	410	410			
20800150	TRENCH BACKFILL	CU YD	29	29			
25000110	SEEDING, CLASS 1A	ACRE	0.75	0.75			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	68			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68	68			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	68			
25100630	EROSION CONTROL BLANKET	SQ YD	3,630	3,630			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	225	225			
28000305	TEMPORARY DITCH CHECKS	FOOT	30	30			
28000400	PERIMETER EROSION BARRIER	FOOT	1,063	1,063			
28000500	INLET AND PIPE PROTECTION	EACH	1	1			
28100109	STONE RIPRAP, CLASS A5	SQ YD	845			845	
28200200	FILTER FABRIC	SQ YD	845			845	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	862	862			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	811	811			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	141	141			
40600300	AGGREGATE (PRIME COAT)	TON	4	4			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	158	158			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	66	66			
40600990	TEMPORARY RAMP	SQ YD	52	52			
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	84	84			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	207	207			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	363	363			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54	54			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	750	750			
44000100	PAVEMENT REMOVAL	SQ YD	194	194			
44000300	CURB REMOVAL	FOOT	43	43			
44000600	SIDEWALK REMOVAL	SQ FT	183	183			
44004250	PAVED SHOULDER REMOVAL	SQ YD	887	887			

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	URBAN		801.FED./201.STATE	
				CONSTRUCTION TYPE CODES			
				ROADWAY 0004	EX SN 019-0013 PR SN 019-0048 0011		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	288	288			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1	
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2			
50105220	PIPE CULVERT REMOVAL	FOOT	131	131			
50200100	STRUCTURE EXCAVATION	CU YD	220			220	
50300100	FLOOR DRAINS	EACH	8			8	
50300225	CONCRETE STRUCTURES	CU YD	214.3			214.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	433.2			433.2	
50300260	BRIDGE DECK GROOVING	SQ YD	642			642	
50300280	CONCRETE ENCASMENT	CU YD	8.5			8.5	
50300300	PROTECTIVE COAT	SQ YD	1,005			1,005	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	126,370			126,370	
50800515	BAR SPLICERS	EACH	481			481	
50901720	BICYCLE RAILING	FOOT	216			216	
50901750	PARAPET RAILING	FOOT	234			234	
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	1,442			1,442	
51202305	DRIVING PILES	FOOT	1,442			1,442	
51203200	TEST PILE METAL SHELLS	EACH	2			2	
51500100	NAME PLATES	EACH	1			1	
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	54	54			
54215550	METAL END SECTIONS 15"	EACH	2	2			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	52			52	
60500060	REMOVING INLETS	EACH	4	4			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	12.5	12.5			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	3	3			
63200310	GUARDRAIL REMOVAL	FOOT	426	426			
64200105	SHOULDER RUMBLE STRIPS	FOOT	1,320	1,320			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	1			
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			

\* SPECIALTY ITEM