

CONCRETE SEALER

STRUCTURE NUMBER	FACILITY CARRIED	APPROXIMATE LOCATION	FEATURE CROSSED	DECK WIDTH FEET	PARAPET SURFACE FEET	MEDIAN SURFACE FEET	DECK LENGTH FEET	SEAL AREA SQ FT	TRAFFIC CONTROL AND PROTECTION STANDARD
NON-INTERSTATE									
046-0023	ILL 1 & 17	MOMENCE	KKK RIVER S BRANCH	52	1		288.3	15,280	701201
046-0027	ILL 17	0.9 MI E OF REDDICK	REDDICK RUN CREEK	32	7.4		115.1	4,535	701201
046-0034	ILL 17	100 FT W US OF 45 & 52	KKK RIVER & PK RD	88.3	6	6.9	631.9	63,948	701201
046-0045	ILL 50	1 MI N JT US 45 & 52	KANKAKEE RIVER	61.2	6.2		595.4	39,763	701201
046-0070	US 52 & 45	1.2 MI S OF I-57	MINNIE CREEK	40			103.8	4,152	701201 *
046-0080	WALDRON RD/FAU 6184	3.4 MI N US 45 & ILL 54	I-57	26	1.4		234.5	6,425	701201
046-0083	STEGER RD	3.2 MI N MANTENO INT	I-57	24	1.8		243.5	6,282	701201
046-0084	LAKE MANTENO RD	1.1 MI N MANTENO RD	I-57	24	1.8		243.5	6,282	701201
046-0085	700ON RD/MS 1025	4.2 MI N ILL 50	I-57	24	1.8		241.1	6,220	701201
046-0089	FAU 6223/OTTO RD	3.4 MI N CHEBANSE INT	I-57 & I C G RR	26.5	6.6		432.8	14,326	701201
046-0111	ILL 1 & 17	MOMENCE	KANKAKEE RIVER	52	1		241	12,773	701501
046-0112	ILL 115,US 45 & 52	0.6 MI S OF ILL 17	KANKAKEE RIVER	46	7.4		561	29,957	701606
046-0113	FAU 6189/RIVER RD	2.3 MI N OF US 45 & 52	I-57	28	7.4		218	7,717	701201
046-0115	ILL 1	4.4 MI S OF ILL 17	DITCH	36	7.4		34	1,476	701201
046-0116	ILL 1	4.0 MI S OF ILL 17	DITCH	36	7.4		39	1,693	701201
046-0117	ILL 1	2.6 MI S OF ILL 17	SPRING CREEK	36	7.4		80	3,472	701201
046-0118	ILL 1	0.8 MI S OF ILL 17	DITCH	36	7.4		43	1,866	701201
046-0119	US 45 & 52	1.0 MI N OF I-57	GARR CREEK	63	7.4		88	6,195	701606
046-0121	US 45 & 52	50 FT N COURT ST IN KKK	SOLDIERS CREEK	91.5	1.6	0.5	107.3	10,194	701601
046-0122	ILL 50	S EDGE OF MANTENO	S BR ROCK CREEK	51.2	1.6		131.2	6,927	701606
046-0125	ILL 50	N LIMITS KANKAKEE	SOLDIER CREEK	65.6	1.6		90	6,048	701602
046-0126	ARMOUR RD/FAU 6176	3.2 MI N OF ILL 17	I-57	53.8	6.2		216.4	12,984	702606
046-0127	ILL 17/FAS 310	2.1 MI SE OF JCT ILL 1 & 17	PIKE CREEK	36	7.4		94	4,080	701201
046-0129	ILL 17	5.0 MI SE OF JCT ILL 1 & 17	BULL CREEK	36	7.4		86.5	3,754	701201
046-0130	ILL 17	1.5 MI E OF REDDICK	MAZON RIVER	32	7.4		90.2	3,554	701201
046-0131	ILL 114	1.7 MI E OF ILL 1 & 17	PIKE CREEK	40	7.4		64	3,034	701201
046-0132	ILL 17	2.0 MI E OF REDDICK	CRANE CREEK	36	7.4		130	5,642	701201
046-0133	ILL 115	15.1 MI W OF US 45	HORSE CREEK	35.4	7.4		98.4	4,212	701501
046-0134	ILL 102	2.2 MI NW OF US 45	DAVIS CREEK	40	1		41.3	1,693	701201 *
046-0137	ILL 113	4.7 MI N OF ILL 17	WILEY CREEK	32	7.6		91.5	3,623	701201
KANKAKEE COUNTY SUB-TOTAL								444,420	
TOTAL								1,041,229	

* STRUCTURE HAS EXISTING PCC OVERLAY. ADDITIONAL DRYING TIME MAY BE REQUIRED.

FILE NAME =	USER NAME = verdinemi	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SEALING SCHEDULE			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\pwwork\verd\emil\d0266091\0366841-sheets.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO. 4 OF 4 SHEETS	STA.	TO STA.	VAR	VARIOUS	6	11
PLOT SCALE = 50.0000' / 1" =		CHECKED -	REVISED -		*D3 BRIDGE DECK SEALING 2012 CONTRACT NO. 66841							
PLOT DATE = 8/1/2011		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							