

# URBAN

## SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0011 PEORIA S.N. 072-0001 90 FED/10 ST	0011 PEORIA S.N. 072-0002 90 FED/10 ST	0004 PEORIA ROADWAY 90 FED/10 ST	0004 PEORIA MOWING 100 ST
20200100	EARTH EXCAVATION	CU YD	2,223			2,223	
20400800	FURNISHED EXCAVATION	CU YD	25			25	
20800150	TRENCH BACKFILL	CU YD	65			65	
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	5,104			5,104	
* 25000210	SEEDING, CLASS 2A	ACRE	1.25			1.25	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	113			113	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	113			113	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	113			113	
* 25100115	MULCH, METHOD 2	ACRE	1.25			1.25	
25100630	EROSION CONTROL BLANKET	SQ YD	1,167			1,167	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250			250	
28000305	TEMPORARY DITCH CHECKS	FOOT	573			573	
28000500	INLET AND PIPE PROTECTION	EACH	6			6	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,555			1,555	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7			7	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	5			5	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	409			409	
40600990	TEMPORARY RAMP	SQ YD	218			218	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,296			1,296	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	394			394	
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	120			120	

\*SPECIALTY  
ITEM