

URBAN
SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0011 PEORIA S.N. 072-0001 90 FED/10 ST	0011 PEORIA S.N. 072-0002 90 FED/10 ST	0004 PEORIA ROADWAY 90 FED/10 ST	0004 PEORIA MOWING 100 ST
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	186,090	93,050	93,040		
50800515	BAR SPLICERS	EACH	172	86	86		
51100100	SLOPE WALL 4 INCH	SQ YD	1,384	692	692		
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	470	235	235		
51202305	DRIVING PILES	FOOT	470	235	235		
51203200	TEST PILE METAL SHELLS	EACH	2	1	1		
51500100	NAME PLATES	EACH	2	1	1		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	EACH	32	16	16		
52100520	ANCHOR BOLTS, 1"	EACH	73	37	36		
54215553	METAL END SECTIONS 18"	EACH	2			2	
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	400			400	
59000200	EPOXY CRACK INJECTION	FOOT	6	1	5		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	236	118	118		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	625			625	
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4			4	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4			4	
63200310	GUARDRAIL REMOVAL	FOOT	625			625	
63304700	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 5	EACH	4			4	
63304805	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 6	EACH	4			4	
64200105	SHOULDER RUMBLE STRIPS	FOOT	16,309			16,309	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2			2	

*SPECIALTY
ITEM

FILE NAME *
0469974-topo.dgn

USER NAME * jhnsantv

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE * 100.0000' / in.

CHECKED -

REVISED -

PLOT DATE * 9/9/2011

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I.
RTE.

74

SECTION

T2(L6VB)BYJ

COUNTY

PEORIA

TOTAL SHEETS

133

SHEET NO.

6

CONTRACT NO. 68874

ILLINOIS FED. AID PROJECT

SCALE:

SHEET NO. 3 OF 5 SHEETS

STA.

TO STA.