

SCHEDULE OF EARTHWORK QUANTITIES - STAGED CONSTRUCTION				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
CROSS-OVER				
STA. 335+00 TO STA. 335+50	11.3	8.48		8.48
STA. 335+50 TO STA. 336+00	26.2	19.65		19.65
STA. 336+00 TO STA. 336+50	44.0	33.00	4.4	28.60
STA. 336+50 TO STA. 337+00	64.3	48.23	22.3	25.93
STA. 337+00 TO STA. 337+50	60.2	45.15	54.9	-9.75
STA. 337+50 TO STA. 338+00	35.8	26.85	72.7	-45.85
STA. 338+00 TO STA. 338+50	18.3	13.73	64.6	-50.88
STA. 338+50 TO STA. 339+00	21.4	16.05	49.1	-33.05
STA. 339+00 TO STA. 339+50	31.9	23.93	37.7	-13.78
STA. 339+50 TO STA. 340+00	33.5	25.13	41.8	-16.68
STA. 340+00 TO STA. 340+50	27.3	20.48	48.2	-27.73
STA. 340+50 TO STA. 341+00	24.3	18.23	68.1	-49.88
STA. 341+00 TO STA. 341+50	39.7	29.78	86.3	-56.53
STA. 341+50 TO STA. 342+00	59.5	44.63	68.6	-23.98
STA. 342+00 TO STA. 342+50	57.0	42.75	36.9	5.85
STA. 342+50 TO STA. 343+00	49.2	36.90	11.8	25.10
STA. 343+00 TO STA. 343+50	49.6	37.20	1.2	36.00
STA. 343+50 TO STA. 344+00	56.5	42.38	2.0	40.38
STA. 344+00 TO STA. 344+50	77.2	57.90	2.0	55.90
STA. 344+50 TO STA. 345+00	61.8	46.35	0.2	46.15
STA. 345+00 TO STA. 345+50	16.0	12.00	0.2	11.80
SUB-TOTAL	865.00	648.75	673.00	-24.25
TOTAL	865	649	673	-25

SCHEDULE OF EARTHWORK QUANTITIES - I-74 MAINLINE STAGE III					
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	TOPSOIL FURNISH & PLACE, 4"
	CU YD	CU YD	CU YD	CU YD	SQ YD
I-74					
STA. 335+00 TO STA. 335+50	21.7	16.28	0.2	16.08	126.33
STA. 335+50 TO STA. 336+00	47.2	35.40	1.0	34.40	252.28
STA. 336+00 TO STA. 336+50	60.9	45.68	25.9	19.78	248.26
STA. 336+50 TO STA. 337+00	71.1	53.33	58.3	-4.98	247.39
STA. 337+00 TO STA. 337+50	79.1	59.33	45.9	13.43	249.59
STA. 337+50 TO STA. 338+00	93.9	70.43	16.2	54.23	249.39
STA. 338+00 TO STA. 338+50	86.8	65.10	4.6	60.50	251.20
STA. 338+50 TO STA. 339+00	69.3	51.98	4.5	47.48	252.33
STA. 339+00 TO STA. 339+50	63.0	47.25	8.1	39.15	253.11
STA. 339+50 TO STA. 340+00	58.0	43.50	10.4	33.10	254.06
STA. 340+00 TO STA. 340+50	62.7	47.03	9.3	37.73	251.98
STA. 340+50 TO STA. 341+00	86.4	64.80	9.6	55.20	252.59
STA. 341+00 TO STA. 341+50	103.6	77.70	21.8	55.90	254.76
STA. 341+50 TO STA. 342+00	88.4	66.30	43.5	22.80	254.67
STA. 342+00 TO STA. 342+50	68.9	51.68	47.2	4.48	255.06
STA. 342+50 TO STA. 343+00	38.9	29.18	30.4	-1.23	258.83
STA. 343+00 TO STA. 343+50	40.5	30.38	15.0	15.38	263.50
STA. 343+50 TO STA. 344+00	74.9	56.18	4.7	51.48	264.87
STA. 344+00 TO STA. 344+50	63.3	47.48	0.9	46.58	266.11
STA. 344+50 TO STA. 345+00	50.7	38.03	0.3	37.73	265.56
STA. 345+00 TO STA. 345+50	28.3	21.23	0.0	21.23	132.09
SUB-TOTAL	1357.6	1018.2	357.8	660.4	5103.9
TOTAL	1,358	1,019	358	661	5,104

SCHEDULE OF GUARDRAIL QUANTITIES						
LOCATION	TBT TYPE 5	TBT TYPE 6	SPB GR TY A 6 FT POSTS	GR AGGREGATE EROSION CONTROL	TEMPORARY SPBGR, TY A	TEMPORARY TBT, TY 1
	EACH	EACH	FT	TON		
I-74 WB LANES						
STA. 345+72.41 TO STA. 346+09.91			37.5	3.80		
STA. 346+09.91 TO STA. 346+59.91	2			10.13	12.5	1
STA. 348+18.53 TO STA. 348+68.53		2		10.13		
STA. 348+68.53 TO STA. 351+18.53			250.0	25.33		
I-74 EB LANES						
STA. 343+15.93 TO STA. 346+03.43			287.5	29.13		
STA. 346+03.43 TO STA. 346+53.43		2		10.13		
STA. 348+12.00 TO STA. 348+62.00	2			10.13	12.5	1
STA. 348+62.00 TO STA. 349+12.00			50.0	5.07		
TOTAL	4	4	625	104	25	2

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
I-74	6
TOTAL	6

MOBILIZATION	
LOCATION	L SUM
I-74	1
TOTAL	1