

PAVEMENT REMOVAL	
LOCATION	SQ YD
TEMPORARY CROSS-OVER	
WB LEG	
STA. 10+00.00 TO STA. 16+77.33	1041.21
EB LEG	
STA. 10+00.00 TO STA. 16+83.84	1,031.22
I-74 (ADJACENT TO WB LANES)	
STA. 337+43.28 TO STA. 341+49.16	627.60
I-74 (ADJACENT TO EB LANES)	
STA. 337+48.04 TO STA. 341+00.00	473.95
TOTAL	3,174

PAVED SHOULDER REMOVAL	
LOCATION	SQ YD
I-74 WB LANES	
RT. STA. 335+34.75 TO STA. 337+43.28	92.69
RT. STA. 341+49.16 TO STA. 343+58.29	92.95
LT. STA. 349+79.76 TO STA. 351+14.76	22.50
I-74 EB LANES	
LT. STA. 335+40.57 TO STA. 337+48.04	92.21
LT. STA. 341+42.52 TO STA. 343+45.85	90.37
RT. STA. 343+20.64 TO STA. 344+71.95	25.22
TEMPORARY CROSS-OVER	
WB LEG	
STA. 10+00.00 TO STA. 12+63.69	117.20
STA. 14+16.36 TO STA. 16+77.33	115.99
EB LEG	
STA. 10+00.00 TO STA. 12+68.41	119.29
STA. 14+17.32 TO STA. 16+83.84	152.29
SUB-TOTAL:	920.70
TOTAL	921

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
I-74 EB LANES	
STA. 345+29.91 TO STA. 346+29.91	26.67
STA. 348+48.53 TO STA. 349+48.53	26.67
I-74 WB LANES	
STA. 345+23.43 TO STA. 346+23.43	26.67
STA. 348+42.00 TO STA. 349+42.00	26.67
TOTAL	107

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
I-74 WB LANES	
STA. 338+70.00 TO STA. 388+05.00	9,047.50
I-74 EB LANES	
STA. 325+00.00 TO STA. 375+00.00	9,166.67
TEMPORARY CROSS-OVER - EB LEG	
STA. 10+00.00 TO STA. 16+83.84	1,367.68
EXISTING CROSS-OVER - EB LEG	
STA. 365+81.00 TO STA. 373+13.20	244.07
TOTAL	19,826

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
I-74 MAINLINE - EB LANES	
STA. 325+00.00 TO STA. 375+00.00	63
I-74 MAINLINE - WB LANES	
STA. 338+70.00 TO STA. 388+05.00	62
TOTAL	125

SCHEDULE OF ROADWAY LIGHTING QUANTITIES		
LOCATION	TEMP. LIGHTING SYSTEM	MAINTENANCE OF TEMPORARY LIGHTING SYSTEM
	L SUM	L SUM
I-74	1	1
TOTAL	1	1

CONCRETE BARRIER REMOVAL AND REPLACEMENT	
LOCATION	FOOT
I-74 EAST CROSS OVER	360
TOTAL	360

SCHEDULE OF GUARDRAIL REMOVAL QUANTITIES			
LOCATION	GUARDRAIL REMOVAL	TBT TYPE 5 REMOVAL	TBT TYPE 6 REMOVAL
	FT	EACH	EACH
I-74 MAINLINE - EB LANES			
STA. 345+72.41 TO STA. 346+09.91	37.5		
STA. 346+09.91 TO STA. 346+59.91		2	
STA. 348+18.53 TO STA. 348+68.53			2
STA. 348+68.53 TO STA. 351+18.53	250.0		
I-74 MAINLINE - WB LANES			
STA. 343+15.93 TO STA. 346+03.43	287.50		
STA. 346+03.43 TO STA. 346+53.43		2	
STA. 348+12.00 TO STA. 348+62.00			2
STA. 348+62.00 TO STA. 349+12.00	50.0		
TOTAL	625	4	4

MATERIAL TRANSFER DEVICE	
LOCATION	TON
POLYMERIZED HMA SURFACE CSE	120
HMA SURFACE CSE	394
HMA BINDER CSE	1,296
TOTAL	1,810

MOWING	
LOCATION	UNIT
I-74	126
TOTAL	126

RAILROAD PROTECTIVE LIABILITY INSURANCE	
LOCATION	L SUM
I-74	1
TOTAL	1

FILE NAME =
D468874-topo.dgn

USER NAME = johnsontv
PLOT SCALE = 1/8"=1'-0"
PLOT DATE = 9/9/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 6 OF 6 SHEETS STA. TO STA.

F.A.J. SECTION COUNTY TOTAL SHEETS SHEET NO.
74 T2(6VBIBY) PEORIA 133 22
CONTRACT NO. 68874
ILLINOIS FED. AID PROJECT