

LOCATION OF WORK: US 136 US 136  
RURAL TWO LANE RURAL TWO LANE  
BRIDGE REPLACEMENT BRIDGE REPLACEMENT  
MCLEAN COUNTY MCLEAN COUNTY  
STA. 415+00 TO STA 442+00 STA. 415+00 TO STA 442+00  
OVER KICKAPOO CREEK OVER KICKAPOO CREEK  
1.3 MIW OF U.S. 51 1.3 MIW OF U.S. 51

FUNDING BREAKOUT: 80% FEDERAL / 20% STATE 80% FEDERAL / 20% STATE  
CONSTRUCTION TYPE CODE: 0004 0011

CODE NO.	ITEM	UNIT	ROADWAY QUANTITY	BRIDGE QUANTITY	TOTAL QUANTITY
X7200201	WIDTH RESTRICTION SIGNING	L SUM	0.0	1.0	1.0
XZ193400	SURVEY MARKER, TYPE 2 (SPECIAL)	EACH	2.0	0.0	2.0
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	0.0	140.0	140.0
Z0002900	BASE COURSE (OPTION)	SQ YD	0.0	500.0	500.0
Z0013798	CONSTRUCTION LAYOUT	L SUM	0.2	0.8	1.0
Z0026407	TEMPORARY SHEET PILING	SQ FT	0.0	932.0	932.0
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	0.0	1,318.0	1,318.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	0.0	2.0	2.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	0.0	2.0	2.0
Z0038700	PERMANENT BENCH MARKS	EACH	0.0	1.0	1.0
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	0.0	150.0	150.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	2.0	0.0	2.0

\* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hoganbj	DESIGNED - BJH 7/12/2011	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\puidot\hoganbj\d0142533\0570	52-sh1-500.dgn	DRAWN -	REVISED -					315	121BR-2	MCLEAN	144	11
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 70552			ILLINOIS FED. AID PROJECT				
PLOT DATE = 8/22/2011	DATE -	REVISED -			SCALE: _____	SHEET NO. 6 OF 6 SHEETS	STA. _____ TO STA. _____					