

SUMMARY OF QUANTITIES

FAP 729 (US-136)
VERMILION CO.
URBAN
TWO LANE
100% STATE

S.N. 092-0144

CONSTRUCTION TYPE CODE: 0014

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	77.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	347.0
40600990	TEMPORARY RAMP	SQ YD	100.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	42.0
48203004	HOT-MIX ASPHALT SHOULDERS, 1 3/4"	SQ YD	350.0
50102400	CONCRETE REMOVAL	CU YD	6.8
50300100	FLOOR DRAINS	EACH	8.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	7.8
50300260	BRIDGE DECK GROOVING	SQ YD	620.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	890.0
50800515	BAR SPLICERS	EACH	10.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	100.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5.0
67100100	MOBILIZATION	L SUM	1.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	362.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	673.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2.0
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2.0
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4.0
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	20.0
Z0002900	BASE COURSE (OPTION)	SQ YD	528.0
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	652.0
Z0012164	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	652.0
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH LESS THAN OR EQUAL TO 5")	SQ FT	90.0
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	14.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	22.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = smsgm	DESIGNED - GMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\p-work\pvidot\smsgm\d0132144\057056-sh-c-500.dgn		DRAWN - GMS	REVISED -			729	38BR-1	VERMILION	25	3
PLOT SCALE = 40.0001' / in.		CHECKED -	REVISED -			CONTRACT NO. 70596				
PLOT DATE = 8/9/2011		DATE -	REVISED -			FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				