

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL TWO-LANE ROADWAY 80% FEDERAL 20% STATE 0014
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	214
2020010	EARTH EXCAVATION	CU YD	20
2030010	CHANNEL EXCAVATION	CU YD	45
2040080	FURNISHED EXCAVATION	CU YD	460
2500020	SEEDING, CLASS 2A	ACRE	0.50
2500040	NITROGEN FERTILIZER NUTRIENT	POUND	45
2500050	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
2500060	POTASSIUM FERTILIZER NUTRIENT	POUND	45
2510063	EROSION CONTROL BLANKET	SQ YD	1288
2800025	TEMPORARY EROSION CONTROL SEEDING	POUND	50
2800040	PERIMETER EROSION BARRIER	FOOT	990
2810017	STONE RIPRAP, CLASS A4	SQ YD	431
2820020	FILTER FABRIC	SQ YD	431
3101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	134
4060010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	107
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	28
40600990	TEMPORARY RAMP	SQ YD	91
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	46
44004250	PAVED SHOULDER REMOVAL	SQ YD	476
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	57
48203100	HOT-MIX ASPHALT SHOULDERS	TON	32
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	3.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4.5
50300260	BRIDGE DECK GROOVING	SQ YD	472
50300300	PROTECTIVE COAT	SQ YD	485
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	4179
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6560
50800515	BAR SPLICERS	EACH	136
50901050	STEEL RAILING, TYPE SM	FOOT	254
51500100	NAME PLATES	EACH	1
5200010	PREFORMED JOINT STRIP SEAL	FOOT	73
52100520	ANCHOR BOLTS, 1"	EACH	10
58700300	CONCRETE SEALER	SQ FT	634
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	25
60500305	FILLING INLETS	EACH	2

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL TWO-LANE ROADWAY 80% FEDERAL 20% STATE 0014
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	525.0
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	885
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	32
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	742
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1053
70400100	TEMPORARY CONCRETE BARRIER	FOOT	437.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	437.5
7800110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	742
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2
78200410	GUARDRAIL MARKERS, TYPE A	EACH	13
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	236
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	5
X0323586	PIPE DRAIN REMOVAL	FOOT	68
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	197
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	465
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	44
Z0002900	BASE COURSE (OPTION)	SQ YD	132
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	33
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	4
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	472
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0038700	PERMANENT BENCH MARKS	EACH	1

* DENOTES SPECIALTY ITEM

FILE NAME : c:\pwork\pudot\craig\08110158\05786319-shr-500.dgn	USER NAME : craig	DESIGNED -	REVISED -
PLOT SCALE : 40.000 / in.	PLOT DATE : 8/3/2011	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	150BR-1	EDGAR	48	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70609	