

SCHEDULE OF QUANTITIES

NOTE:
SEVERAL PAY ITEMS APPEAR AT MULTIPLE LOCATIONS THROUGHOUT THE PLANS.
FOR GRAND TOTALS, SEE ALL SCHEDULES, PLAN SHEETS AND DETAILS.

CLASS B PATCHING SCHEDULE, 12"

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200994	44200998	44201000	44201299	44213200	44213204	44213100
				TYPE II, 12"	TYPE III, 12"	TYPE IV, 12"	DOWELL BARS, 1 1/2"	SAW CUTS (FT)	TIE BARS 3/4"	PAVEMENT FABRIC (SQ YD)
				(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(FT)	(EACH)	(SQ YD)
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP CB	MISC.	12.00	16.00		21.33		28.00	72.00		21.33
E.B. RAMP CB	MISC.	20.00	20.00			44.44	54.00	100.00	10.00	44.44
E.B. RAMP BD	MISC.	20.00	20.00			44.44	54.00	100.00	10.00	44.44
E.B. RAMP BD	MISC.	12.00	16.00		21.33		28.00	72.00		21.33
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
E.B. RAMP BD	MISC.	6.00	16.00	10.67			28.00	60.00		
TOTAL =				170.72	42.66	88.88	612.00	1304.00	20.00	131.54
USE =				171.00	43.00	89.00	612.00	1304.00	20.00	132.00
				(SQ YD)	(SQ YD)	(SQ YD)	(EACH)	(FT)	(EACH)	(SQ YD)

NOTE:
THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.
THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED
IN G.N.-442B

CLASS D PATCHING SCHEDULE, 8"

LOCATION	STATION	NUMBER OF PATCHES	LENGTH (FT)	WIDTH (FT)	44201741	44201745	44201747
					TYPE II, 8"	TYPE III, 8"	TYPE IV, 8"
					(SQ YD)	(SQ YD)	(SQ YD)
FAS 1478	MISC.	12.00	6.00	14.00	112.00		
FAS 1478	MISC.	8.00	12.00	14.00		149.33	
FAS 1478	MISC.	4.00	20.00	14.00			124.44
TOTAL =					112.00	149.33	124.44
USE =					112.00	150.00	125.00
					(SQ YD)	(SQ YD)	(SQ YD)

NOTES:
ON FAS 1478 AN APPROXIMATE QUANTITY OF THE VARIOUS TYPES
OF CLASS D PATCHES WAS USED TO ESTABLISH PAY ITEMS FOR
THIS SECTION OF ROADWAY. THE ACTUAL LOCATION AND SIZE
SHALL BE FIELD VERIFIED AS SPECIFIED IN G.N.-442B.

THE LOCATION OF THE 8" PATCHES OCCUR WHERE THE HOT-MIX
ASPHALT RESURFACING WILL BE MILLED TO BARE CONCRETE. THE
PATCHING OPERATIONS SHALL NOT BE COMPLETED UNTIL AFTER
THE EXISTING HOT-MIX ASPHALT MATERIAL IS REMOVED.

THE PAVEMENT NORTH OF THE ABUTMENT ON S.N. 057-0132 SHALL
ONLY BE PATCHED IF DEEMED NECESSARY BY THE ENGINEER.

CLASS B PATCHING SCHEDULE, 13"

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44201007	44201011	44201299	44213200	44213100
				TYPE II, 13"	TYPE III, 13"	DOWELL BARS, 1 1/2"	SAW CUTS (FT)	PAVEMENT FABRIC (SQ YD)
				(SQ YD)	(SQ YD)	(EACH)	(FT)	(SQ YD)
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP DA	MISC.	12.00	16.00		21.33		28.00	72.00
W.B. RAMP DA	MISC.	12.00	16.00			21.33	28.00	72.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	6.00	16.00	10.67			28.00	60.00
W.B. RAMP AC	MISC.	12.00	16.00		21.33		28.00	72.00
W.B. RAMP AC	MISC.	12.00	16.00			21.33	28.00	72.00
TOTAL =				170.72	42.66	504.00	1104.00	42.66
USE =				171.00	43.00	504.00	1104.00	43.00
				(SQ YD)	(SQ YD)	(EACH)	(FT)	(SQ YD)

NOTE:
THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.
THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED
IN G.N.-442B

PARTIAL DEPTH PAVEMENT PATCHING

LOCATION	STATION	NUMBER OF PATCHES	LENGTH (FT)	WIDTH (FT)	44022029	X4421000
					PARTIAL DEPTH REMOVAL 3" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
FAS 1478	MISC.	20.00	4.00	14.00	124.44	20.91
FAS 1478	MISC.	8.00	6.00	14.00	74.67	12.54
FAS 1478	MISC.	4.00	10.00	14.00	62.22	10.45
TOTAL =					261.33	43.90
USE =					262.00	44.00
					SQ YD	TON

NOTES:
ON FAS 1478 AN APPROXIMATE QUANTITY OF PARTIAL DEPTH PATCHES
WAS USED TO ESTABLISH PAY ITEMS FOR THIS SECTION OF ROADWAY.
THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED
IN G.N.-442B.

THE LOCATION OF THE 3" PATCHES OCCUR WHERE THE HOT-MIX ASPHALT
RESURFACING WILL BE MILLED TO BARE CONCRETE. THE PATCHING
OPERATIONS SHALL NOT BE COMPLETED UNTIL AFTER THE EXISTING
HOT-MIX ASPHALT MATERIAL IS REMOVED.

THE PAVEMENT NORTH OF THE ABUTMENT ON S.N. 057-0132 SHALL ONLY
BE PATCHED IF DEEMED NECESSARY BY THE ENGINEER.