

SCHEDULE OF QUANTITIES

SUMMARY OF DRAINAGE STRUCTURE IMPROVEMENT PAY ITEMS

NOTE:
SEVERAL PAY ITEMS APPEAR AT MULTIPLE LOCATIONS THROUGHOUT THE PLANS.
FOR GRAND TOTALS, SEE ALL SCHEDULES, PLAN SHEETS AND DETAILS.

		20200100	20400800	20800150	21400100	25000210	25000400	25000500	25000600	25100115	28000250	28000400	28000500	
		EARTH EXCAVATION	FURNISHED EXCAVATION	TRENCH BACKFILL	GRADING AND SHAPING DITCHES	SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	
LOCATION	STATION	(CU YD)	(CU YD)	(CU YD)	(FOOT)	(ACRE)	(POUND)	(POUND)	(POUND)	(ACRE)	(POUND)	(FOOT)	(EACH)	
#1	W.B.	1160+50.00	8.30	7.00		0.002	0.20	0.20	0.20	0.002	0.20			
#2	W.B.	1172+65.00			20.00	0.009	0.81	0.81	0.81	0.009	0.90	30.00		
#3	E.B. & W.B.	1191+00.00			44.00	0.072	6.48	6.48	6.48	0.072	7.20	60.00	1.00	
#4	E.B. & W.B.	1232+00.00	14.00	13.00		0.003	0.27	0.27	0.27	0.003	0.30			
#5	W.B.	112+00.00	7.20			0.003	0.27	0.27	0.27	0.003	0.30			
#6	MEDIAN & E.B.	123+20.00		12.00		0.006	0.54	0.54	0.54	0.006	0.60		2.00	
#7	W.B.	187+25.00												
#8	E.B.	212+00.00	4.40			0.001	0.09	0.09	0.09	0.001	0.10			
#9	E.B.	238+00.00	7.20			0.003	0.27	0.27	0.27	0.003	0.30			
#10	MEDIAN	247+00.00		6.00		0.003	0.27	0.27	0.27	0.003	0.30		1.00	
#11	E.B. & W.B.	254+85.00												
#12	RAMP AC	9+93.00	7.20			0.003	0.27	0.27	0.27	0.003	0.30			
#13	RAMP DA	10+35.00	18.70			0.006	0.54	0.54	0.54	0.006	0.60			
#14	FAS 1478	54+00.00			24.00	0.012	1.08	1.08	1.08	0.012	1.20		1.00	
TOTAL =			67.00	18.00	20.00	88.00	0.123	11.09	11.09	11.09	0.123	12.30	90.00	5.00
USE =			67.00	18.00	20.00	88.00	0.200	13.00	13.00	13.00	0.200	13.00	90.00	5.00
			CU YD	CU YD	CU YD	FOOT	ACRE	POUND	POUND	POUND	ACRE	POUND	FOOT	EACH

		28100107	28200200	44004250	48203100	54248510	54390110	66500105	X2010350	X3112700	X6650200	Z0022800	
		STONE RIPRAP CLASS A4	FILTER FABRIC	PAVED SHOULDER REMOVAL	HOT-MIX ASPHALT SHOULDERS	CONCRETE COLLAR	INSERTION CULVERT LINER, 14"	WOVEN WIRE FENCE, 4'	TREE REMOVAL ACRES, SPECIAL	COARSE AGGREGATE FILL	WOVEN WIRE FENCE (SPECIAL)	FENCE REMOVAL	
LOCATION	STATION	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(CU YD)	(FOOT)	(FOOT)	(ACRE)	(TON)	(FOOT)	(FOOT)	
#1	W.B.	1160+50.00		7.00	6.00	0.90							
#2	W.B.	1172+65.00						0.009					
#3	E.B. & W.B.	1191+00.00						0.072		50.00		50.00	
#4	E.B. & W.B.	1232+00.00	14.00	14.00		0.90		60.00				60.00	
#5	W.B.	112+00.00				0.45							
#6	MEDIAN & E.B.	123+20.00					40.00	40.00	0.040			40.00	
#7	W.B.	187+25.00	50.00	50.00									
#8	E.B.	212+00.00		16.00				100.00	0.035	6.00		100.00	
#9	E.B.	238+00.00				0.45							
#10	MEDIAN	247+00.00					20.00						
#11	E.B. & W.B.	254+85.00	108.00	108.00						100.00		100.00	
#12	RAMP AC	9+93.00				0.45							
#13	RAMP DA	10+35.00				1.14							
#14	FAS 1478	54+00.00							0.012				
TOTAL =			172.00	188.00	7.00	6.00	4.29	60.00	200.00	0.168	6.00	150.00	350.00
USE =			172.00	188.00	7.00	6.00	4.50	60.00	200.00	0.200	6.00	150.00	350.00
			SQ YD	SQ YD	SQ YD	TON	CU YD	FOOT	FOOT	ACRE	TON	FOOT	FOOT