

SCHEDULE OF QUANTITIES

NOTE:
SEVERAL PAY ITEMS APPEAR AT MULTIPLE LOCATIONS THROUGHOUT THE PLANS.
FOR GRAND TOTALS, SEE ALL SCHEDULES, PLAN SHEETS AND DETAILS.

78000100 THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS

LOCATION	STATION	SYMBOL	QUANTITY (SQ FT)
FAS 1478	39+89.00	LT. TURN	15.60
FAS 1478	40+53.00	LT. TURN	15.60
FAS 1478	41+17.00	LT. TURN	15.60
FAS 1478	41+81.00	LT. TURN	15.60
FAS 1478	49+54.00	LT. TURN	15.60
FAS 1478	50+18.00	LT. TURN	15.60
FAS 1478	50+82.00	LT. TURN	15.60
FAS 1478	51+46.00	LT. TURN	15.60
TOTAL =			124.80 SQ FT
USE =			125.00 SQ FT
RURAL =			63.00 SQ FT
OTHER =			62.00 SQ FT

78300100 PAVEMENT MARKING REMOVAL

LOCATION	STATION	TO	STATION	SYMBOL	QUANTITY (SQ FT)
FAS 1478	LT.	39+71.00	41+81.00		70.00
FAS 1478	LT.	39+89.00		LT. TURN	15.60
FAS 1478	LT.	40+76.00		LT. TURN	15.60
FAS 1478	LT.	41+63.00		LT. TURN	15.60
FAS 1478	RT.	49+54.00	51+64.00		70.00
FAS 1478	RT.	49+72.00		LT. TURN	15.60
FAS 1478	RT.	50+59.00		LT. TURN	15.60
FAS 1478	RT.	51+46.00		LT. TURN	15.60
TOTAL =					233.60 SQ FT
USE =					234.00 SQ FT

NOTE:
PAVEMENT MARKING REMOVAL WILL BE REQUIRED ON FAS 1478
PRIOR TO STAGE CONSTRUCTION OF S.N. 057-0132. THE EXISTING
TURN ARROWS AND LEFT TURN LANE STRIPING SHALL BE REMOVED
TO ELIMINATE CONFLICTS WITH TEMPORARY PAVEMENT MARKINGS
FOR STAGE I AND STAGE II CONSTRUCTION.

63400105 GUARD POSTS

X6340205 GUARD POSTS REMOVAL

LOCATION	STATION	63400105	X6340205
		QUANTITY (EACH)	QUANTITY (EACH)
MEDIAN DITCH CHECK	1160+50.00	6.0	6.0
MEDIAN DITCH CHECK	1172+65.00	6.0	7.0
MEDIAN DITCH CHECK	1191+00.00	6.0	5.0
S.N. 057-0130 PIER	1193+89.94	32.0	16.0
MEDIAN DITCH CHECK	1208+00.00	6.0	7.0
MEDIAN DITCH CHECK	112+00.00	6.0	7.0
MEDIAN DITCH CHECK	134+00.00	6.0	7.0
S.N. 057-0131 PIER	162+21.90	36.0	0.0
MEDIAN DITCH CHECK	187+25.00	6.0	6.0
MEDIAN DITCH CHECK	212+00.00	10.0	8.0
MEDIAN DITCH CHECK	221+00.00	6.0	7.0
MEDIAN DITCH CHECK	238+00.00	6.0	5.0
MEDIAN DITCH CHECK	247+00.00	6.0	7.0
MEDIAN DITCH CHECK	276+00.00	6.0	6.0
S.N. 057-0132 PIER	308+57.53	24.0	0.0
MEDIAN DITCH CHECK	326+90.00	6.0	5.0
MEDIAN DITCH CHECK	338+00.00	6.0	5.0
MEDIAN DITCH CHECK	347+00.00	6.0	4.0
MEDIAN DITCH CHECK	352+00.00	6.0	5.0
TOTAL =		192.0 EACH	113.0 EACH

NOTE:
GUARD POSTS ARE CALCULATED AT ALL EXISTING MEDIAN
DITCH CHECKS AND PROPOSED IMPACT ATTENUATOR LOCATIONS.
THE ACTUAL QUANTITY REQUIRED FOR GUARD POST REMOVAL
AND GUARD POSTS MAY VARY PER LOCATION AND SHALL BE
DETERMINED BY THE ENGINEER.

Z0008758 AERIAL SPEED CHECK MARKING

STATION	LENGTH (FT)	COLOR
E.B. 1223+66.00	12.00	WHITE
E.B. 1230+26.00	12.00	WHITE
W.B. 1223+66.00	12.00	WHITE
W.B. 1230+26.00	12.00	WHITE
TOTAL =		48.00 FT

78004210 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
E.B. C.L.	1110+47.50		1125+96.05	400.00	WHITE
E.B. C.L.	1127+93.71		1136+00.00	210.00	WHITE
E.B. C.L.	1136+00.00		1241+13.89 (BK)	2630.00	WHITE
E.B. C.L.	100+00.00 (AH)		375+90.88	6910.00	WHITE
W.B. C.L.	1110+47.50		1126+47.10	410.00	WHITE
W.B. C.L.	1128+14.80		1136+00.00	200.00	WHITE
W.B. C.L.	1136+00.00		1241+13.89 (BK)	2630.00	WHITE
W.B. C.L.	100+00.00 (AH)		375+86.78	6910.00	WHITE
TOTAL =					20300.00 FT
URBAN =					1220.00 FT
RURAL =					19080.00 FT