

QUANTITIES FOR	CONCRETE PIPES
INSIDE DIAMETER OF PIPE	ESTIMATED CLASS SI CONCRETE REQUIRED 20" (500 mm) WIDTH
INCH (mm)	CU. YD. (m3)
4" (100)	0.14 (0.11)
6" (150)	0.16 (0.12)
8" (200)	0.19 (0.14)
10" (250)	0.22 (0.17)
12" (300)	0.25 (0.19)
15" (375)	0.30 (0.23)
18" (450)	0.35 (0.27)
24" (600)	0.45 (0.35)
30" (750)	0.57 (0.43)
36" (900)	0.69 (0.53)
42" (1050)	0.83 (0.63)
48" (1200)	0.97 (0.74)
54" (1350)	1.12 (0.86)
60" (1500)	1.28 (0.98)

QUANTITIES FOR METAL PIPES					
INSIDE DIAMETER	ESTIMATED				
OF PIPE	CLASS SI CONCRETE				
	REQUIRED				
	20" (500 mm) WIDTH				
INCH (mm)	CU. YD. (m3)				
4" (100)	0.12 (0.09)				
6" (150)	0.14 (0.11)				
8" (200)	0.16 (0.12)				
10" (250)	0.19 (0.14)				
12" (300)	0.21 (0.16)				
15" (375)	0.25 (0.19)				
18" (450)	0.29 (0.22)				
24" (600)	0.38 (0.29)				
30" (750)	0.47 (0.36)				
36" (900)	0.59 (0.45)				
42" (1050)	0.69 (0.53)				
48" (1200)	0.81 (0.62)				
54" (1350)	0.93 (0.71)				
60" (1500)	1.05 (0.81)				

GENERAL NOTES

- 1. CLASS SI CONCRETE SHALL BE USED THROUGHOUT.
- 2. WHEN CONCRETE COLLARS ARE USED TO CONNECT PIPES OF DIFFERENT OUTSIDE DIAMETERS, THE CONCRETE COLLAR SHALL BE FORMED USING THE LARGEST OUTSIDE DIAMETER (SEE END VIEW).
- 3. THE WIRE MESH SHALL WEIGH NOT LESS THAN 54#/100 SQ. FT. (2.63 kg/m²).
- 4. WHEN CONCRETE COLLARS ARE CONSTRUCTED ADJACENT TO AN EXISTING CONCRETE STRUCTURE (HEADWALLS, ETC.) EXPANSION BOLTS, SHALL BE USED AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE, EACH, FOR EXPANSION BOLTS OF THE SIZE SPECIFIED IN THE PLANS.
- 5. CONCRETE COLLARS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE, PER CUBIC YARD (CUBIC METER), FOR CONCRETE COLLARS INCLUDING ALL MATERIAL AND LABOR SPECIFIED TO COMPLETE THE WORK IN PLACE.

TO STA.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

DISTRICT 5 DETAIL NO. 54248510

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(57-23,57-24)RS-1	MCLEAN	175	168
		CONTRACT	NO 7	20.40

FILE NAME =	USER NAME = piersonbr	DESIGNED -	REVISED - 12/06	
c:\pw_work\pwidot\piersonbr\d0184863\D57	0648-sht-details.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS
	PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION
	PLOT DATE = 8/26/2011	DATE -	REVISED -	

TION SCALE:

CONCRETE COLLAR

SHEET NO.1 OF 1 SHEETS STA.

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | NO. 70648