

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	FUNDING SOURCES										
			CONSTRUCTION CODE	Veterans interconnect Peoria Rd to Browning Road	Veterans Pkwy and Bruns Lane	Veterans Pkwy and Palomino Road	Veterans interconnect - Palomino to Washington	Veterans Pkwy and Lawrence Avenue	Monroe interconnect - Clocktower to Mountcastle	Old Jacksonville interconnect - Veterans to Koke Mill	Veterans interconnect - Monroe to Wabash	Iles interconnect - White Oaks Plaza to Koke Mill	Wabash Avenue and Koke Mill
			0021	90% Fed 10% State	90% Fed 5% State 5% City	90% Fed 5% State 5% City	90% Fed 10% State	90% Fed 5% State 5% City	90% Fed 5% State 5% City	90% Fed 5% State 5% City	90% Fed 10% State	90% Fed 5% State 5% City	90% Fed 5% State 5% City
TOTAL	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY		
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1			1							
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	3		1			2					
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1								
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	30		12	12		6					
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	20		10	10							
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	96		37	33		26					
87900200	DRILL EXISTING HANDHOLE	EACH	13	1	4	4			2	2			
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2							
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12		4	4		4					
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4		2	2							
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3		1	2							
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2			2							
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3 SECTION, 2-5 SECTION, BRACKET MOUNTED	EACH	2		1			1					
88040320	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-4 SECTION, 2-5 SECTION, BRACKET MOUNTED	EACH	1		1								
88040330	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1								
88040360	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1					1					
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNT, COUNTDOWN TIMER	EACH	1					1					
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	27		11	10		6					
88800100	PEDESTRIAN PUSH-BUTTON	EACH	1					1					
89502200	MODIFY EXISTING CONTROLLER	EACH	2		1	1							
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	8	2			2			2	1	1	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	11,600		1,141	1,963	7,027	1,469					
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	838		518	320							
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3		1	1		1					
89502380	REMOVE EXISTING HANDHOLE	EACH	1				1						
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10		4	4		2					
X0323986	RELOCATE EXISTING VIDEO VEHICLE DETECTOR	EACH	2					2					
X0325469	MODIFY EXISTING TRAFFIC SIGNAL BACKPLATE	EACH	43				10	4		29			
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	477		219	76		162		10	10		
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	
X8130115	DRILL EXISTING JUNCTION BOX	EACH	1	1									
X8804030	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3 SECTION, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	3		1	2							

USER NAME : sparksgu	DESIGNED -	REVISED -
PLOT SCALE : 40,0000' / 1"	DRAWN - BDM	REVISED -
PLOT DATE : Aug-25-2011 09:00:06AM	CHECKED - JSA	REVISED -
	DATE - 7/15/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	*	SANGAMON	42	3
* D6 TRAF SIGNAL MOD 2011-1		CONTRACT NO. 72E38		
ILLINOIS FED. AID PROJECT				

FILE NAME : c:\pwork\pvidot\sparksgu\d0278783\0672E38 shi 500.dgn