

November 3, 2011

SUBJECT: FAS Route 2704 (Old US 50) Project ACRS-2704 (001) Section 12B-1(1) & 12B-1(2) Clay County Contract No. 74116 Item No. 120, November 18, 2011 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 8 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E. Acting Engineer of Design and Environment

Verter abschbyon P.E.

By: Ted B. Walschleger, P. E. Engineer of Project Management

cc: Roger Driskell, Region 4, District 7; Mike Renner; D.Carl Puzey; Estimates

TBW:DB:jc

FAS Route 2704 (Old US 50) Project ACRS-2704 (001) Section 12B-1(1) & 12B-1(2) Clay County Contract No. 74116

			Contra
CZ-84	8.9 (480)	SPZ-23	21.4 (1153)
CZ-95RD	10.2 (550)	CZ-114	21.7 (1165)
CZ-95	10.5 (566)	SZ-27	22.4 (1206)
SZ-18	10.9 (588)	PLZ-25	23.0 (1236)
SPZ-19.5	11.2 (604)	SPZ-26	24.4 (1311)
CZ-101	11.3 (609)	CZ-128	24.8 (1332)
SZ-20	12.0 (648)	PZ-27	25.5 (1371)
CZ-107	12.1 (653)	CZ-141	27.9 (1497)
SZ-21	12.5 (674)	PZC-18	28.3 (1520)
SPZ-22	12.7 (682)	CZ-148	29.4 (1581)
CZ-113	12.9 (695)	PZ-35	43.6 (2344)
		PZ-40	54.6 (2932)
SZ-18 SPZ-19.5 CZ-101 SZ-20 CZ-107 SZ-21 SPZ-22 CZ-113	10.9 (588) 11.2 (604) 11.3 (609) 12.0 (648) 12.1 (653) 12.5 (674) 12.7 (682) 12.9 (695)	PLZ-25 SPZ-26 CZ-128 PZ-27 CZ-141 PZC-18 CZ-148 PZ-35 PZ-40	23.0 (1236) 24.4 (1311) 24.8 (1332) 25.5 (1371) 27.9 (1497) 28.3 (1520) 29.4 (1581) 43.6 (2344) 54.6 (2932)

* Effective Section Modulus is computed by taking the effects of corrosion loss allowances and the Hartman reduction factor.

The selection of the sheet pile section shall not relieve the Contractor of the responsibility to satisfy all details including minimum clearances, cover, embedments, reinforcement, shear stud locations, interlocking, and field cutting. Any modifications of the plans to accommodate the Contractor's selection shall be paid for by the Contractor and subject to the approval of the Engineer.

<u>Construction.</u> The Contractor shall verify locations of all underground utilities before driving any sheet piling. Any disturbance or damage to existing structures, utilities or other property, caused by the Contractor's operation, shall be repaired by the Contractor in a manner satisfactory to the Engineer at no additional cost to the Department. The Contractor shall be responsible for determining the appropriate equipment necessary to drive the sheeting to the tip elevation(s) specified on the plans or according to the Contractor's approved design. The sheet piling shall be driven, as a minimum, to the tip elevation(s) specified, prior to commencing any related construction. If unable to reach the minimum tip elevation, the adequacy of the sheet piling design will require re-evaluation by the Department prior to allowing construction adjacent to the sheet piling in question.

Basis of Payment. The permanent steel sheet piling and its' installation shall be included in the contract unit price per each for BOX CULVERT END SECTIONS, CULVERT NO. 1.

WEEP HOLE DRAINS FOR ABUTMENTS, WINGWALLS, RETAINING WALLS AND CULVERTS

Effective: January 27, 2011

Delete the last paragraphs of 205.05 and 502.10 and replace with the following.

If a geocomposite wall drain according to Section 591 is not specified, a prefabricated geocomposite strip drain, meeting the requirements of Article 1040.07, shall be placed at the back of each drain hole. The strip drain shall be 24 inches (600 mm) wide and 48 inches (1.220 m) tall. The strip drain shall be centered over and attached to the drain hole with the bottom located 12 inches (300 mm) below the bottom of the drain hole. All form boards or other obstructions shall be removed from the drain holes before placing any geocomposite strip drain. Revised 11/3/2011