





LEGEND

-  TEMPORARY BRIDGE TRAFFIC SIGNALS
-  IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3
-  TEMPORARY CONCRETE BARRIER
-  STOP BAR

TEMPORARY CONCRETE BARRIER

137+08 TO 138+08	100.0 FOOT
138+08 TO 140+20	212.5 FOOT
140+20 TO 141+20	100.0 FOOT
TOTAL =	413.0 FOOT

TEMPORARY BRIDGE TRAFFIC SIGNALS

S. N. 070-0050	1.0 EACH
TOTAL =	1.0 EACH

PAVEMENT REMOVAL

138+31 TO 138+92	118.6 SQ YD
139+45 TO 139+97	101.1 SQ YD
TOTAL =	220.0 SQ YD

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

137+08	1.0 EACH
141+20	1.0 EACH
TOTAL =	2.0 EACH

FILE NAME =	USER NAME = swartzrw	DESIGNED -	REVISED -
ct:\pw\work\p\dot\swartzrw\dms52812\d77	280-sht-stage1.dgn	DRAWN -	REVISED -
	PLOT SCALE = 20.0000 "/td> <td>CHECKED -</td> <td>REVISED -</td>	CHECKED -	REVISED -
	PLOT DATE = 8/9/2011	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

STAGE I CONSTRUCTION			
SCALE: 20	SHEET NO. 2 OF 3 SHEETS	STA. 137+00	TO STA. 142+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	(102BY)B-1	MOULTRIE	48	12
			CONTRACT NO. 74280	
ILLINOIS FED. AID PROJECT				