

| SUMMARY OF QUANTITIES (Cont'd) | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | |
|--------------------------------|---|--------|------------------|------------------------|------------------|------------------|
| CODE NO | ITEM | UNIT | | 0021 URBAN MACON | 0021 RURAL MACON | 0021 RURAL PIATT |
| 54001003 | BOX CULVERT END SECTIONS, CULVERT NO. 3 | EACH | 2 | | 2 | |
| 54020602 | PRECAST CONCRETE BOX CULVERT 6' X 2' (M273) | FOOT | 56 | | 56 | |
| 54021002 | PRECAST CONCRETE BOX CULVERT 10' X 2' (M273) | FOOT | 56 | | 56 | |
| 54021202 | PRECAST CONCRETE BOX CULVERTS 12' X 2' (M273) | FOOT | 124 | | 124 | |
| 54213663 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" | EACH | 2 | | 2 | |
| 54213666 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21" | EACH | 6 | 2 | 4 | |
| 542A0223 | PIPE CULVERTS, CLASS A, TYPE 1 18" | FOOT | 40 | | 40 | |
| 542A0226 | PIPE CULVERTS, CLASS A, TYPE 1 21" | FOOT | 152 | 56 | 96 | |
| 64200105 | SHOULDER RUMBLE STRIPS | FOOT | 67945 | 10326 | 48687 | 8932 |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE I | EACH | 1 | | 1 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 1 | 4 | 1 |
| 67100100 | MOBILIZATION | L SUM | 1 | 0.1 | 0.8 | 0.1 |
| 70100405 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 | EACH | 3 | | 3 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | | 1 | |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 0.1 | 0.8 | 0.1 |
| 70101830 | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 | L SUM | 1 | 0.5 | 0.5 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 12 | 2 | 8 | 2 |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 3 | | 3 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 2256 | 256 | 2000 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 84194 | 12002 | 61707 | 10485 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SO FT | 188 | 21 | 167 | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 800 | 75 | 725 | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 487.5 | 75 | 412.5 | |
| *78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 84194 | 12002 | 61707 | 10485 |
| *78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 71 | 8 | 63 | |
| Z0023602 | GRANULAR CULVERT BACKFILL | CU YD | 50 | | 50 | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 6 | 1 | 5 | |
| Z0030260 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 2 | | 2 | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 6 | 1 | 5 | |
| Z0054505 | ROCK FILL - REPLACEMENT | TON | 148 | | 148 | |
| Z0070202 | SURVEY MARKER VAULT | EACH | 1 | | 1 | |

* SPECIALTY ITEM

* MACON & PIATT

| | | | | | | | | | | | | | |
|--|-----------------------------|------------|-----------|---|------------------------------|-------------------------|------|-------------|---------|----------|--------------------|-----------|---|
| FILE NAME = | USER NAME = swartzrw | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| c:\pwwork\pwwork\swartzrw\d0156168\77422-sht-soq.dgn | | DRAWN - | REVISED - | | SCALE: NA | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA. | 741 | (11,12)T | * | 85 | 4 |
| | PLOT SCALE = 100.0000' / 1" | CHECKED - | REVISED - | | | | | | | | CONTRACT NO. 74422 | | |
| | PLOT DATE = 8/16/2011 | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | | | | |