

80% FED.
20% STATE

80% FED.
20% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14			14
35501336	HOT-MIX ASPHALT BASE COURSE, 13"	SQ YD	60	60		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3451	3451		
40600300	AGGREGATE (PRIME COAT)	TON	69	69		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1449	1449		
40600990	TEMPORARY RAMP	SQ YD	543	543		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2899	2899		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	348	348		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	34510	34510		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	178	178		
44000600	SIDEWALK REMOVAL	SO FT	348	348		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	50	50		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	20	20		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4680	4680		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	520	520		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1052	1052		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10313	10313		
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2555	2555		
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	172	172		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	423	423		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	60	60		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	0021
*80500100	SERVICE INSTALLATION, TYPE A	EACH	3			
*81028310	UNDERGROUND CONDUIT, PVC, 3/4" DIA.	FOOT	1036			1036
*81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	955			955
*81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	283			283
*81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	622			622
*81028400	UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	36			36
*81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	18		18	
*81400100	HANDHOLE	EACH	12			12
*81400300	DOUBLE HANDHOLE	EACH	2			2
*81500100	GULFBOX JUNCTION	EACH	7			7
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1513			1513
*83057170	LIGHT POLE, WOOD, 35 FOOT, CLASS 3	EACH	3		2	1
*85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2			2
*85800100	FLASHER CONTROLLER	EACH	1		1	
*87200400	SPAN WIRE	FOOT	94		94	
*87200500	TETHER WIRE	FOOT	94		94	
*87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	368			368
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3872			3872
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	5270			5270
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1PAIR	FOOT	5992			5992
*87301800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2C	FOOT	157			157
*87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	137			137
*87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1416			1416
*87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	75		75	
*87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	6			6
*87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	7			7
*87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	2			2
*87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1			1
*87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	2			2

FILE NAME =	USER NAME = teasleyk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pilot\teasleyk\4449\4449-shr-soq.dgn	4449-shr-soq.dgn	DRAWN -	REVISED -			827	*	Wabash	44	3	
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -			CONTRACT NO. 74449					
PLOT DATE = 9/7/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.				