

RESURFACING SCHEDULE

STATION TO STATION	LENGTH FOOT	AVERAGE PAVEMENT WIDTH FOOT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	LEVELING BINDER (MACHINE METHOD), N90 TON	TEMPORARY RAMP SQ YD
851+22.00 TO 860+10.00	888.0	22.0	2170.7	2170.7	217.1	4.3	182.3	91.2	36.7
860+10.00 TO 893+45.00	3335.0	27.0	10005.0	10005.0	1000.5	20.0	840.4	420.2	0.0
893+45.00 TO 897+00.00	355.0	34.0	1341.1	1341.1	134.1	2.7	112.7	56.3	0.0
897+00.00 TO 897+40.00	40.0	40.0	177.8	177.8	17.8	0.4	14.9	7.5	0.0
9TH STREET & WALNUT INTERSECTION			3776.6	3776.6	377.7	7.6	317.2	158.6	226.7
41+00.00 TO 68+40.00	2740.0	43.0	13091.1	13091.1	1309.1	26.2	1099.7	549.8	0.0
3RD STREET & WALNUT INTERSECTION			1737.5	1737.5	173.7	3.5	145.9	73.0	80.0
70+40.00 TO 74+28.00	388.0	30.0	1293.3	1293.3	129.3	2.6	108.6	54.3	0.0
74+28.00 TO 75+02.00	74.0	15.0	123.3	123.3	12.3	0.2	10.4	5.2	50.0
75+60.00 TO 76+00.00	40.0	15.0	66.7	66.7	6.7	0.1	5.6	2.8	50.0
76+41.00 TO 76+83.00	42.0	15.0	70.0	70.0	7.0	0.1	5.9	2.9	50.0
76+83.00 TO 78+80.00	197.0	30.0	656.7	656.7	65.7	1.3	55.2	27.6	50.0
TOTALS	8099.0		34510.0	34510.0	3451.0	69.0	2899.0	1449.0	543.0

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\pwork\teasleyck\0177977\0774449-sht-schedule.dgn	PLOT SCALE = 50.0000' / 1" =	DRAWN -	REVISED -					827	*	Wabash	44	7
PLOT DATE = 9/7/2011	DATE -	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 74449				
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							

\*(103,104)RS-1, (122)RS-2