



Schedule of Existing Monuments

Station	Offset	Description
39+51.10 (Walnut)	0	Found Alum. IDOT disk flush in bit pavt
50+00 (9th Street)		stamped POT 18+919 metric stationing
857+00	0	Found Mag Nail with washer - POT
854+76.45	0	Found Mag Nail with washer - PT
0+00 (IL 15) (Walnut Street)	0	Found PK Nail
12+21.58 BK = 1012+15.28 AH	0	Found PK Nail - PC 12+21.58
20+00	0	Found PK - possible Sta of Nail is 100 feet from bridge abutment. Did not find PT

FILE NAME = c:\p\work\p\dot\teasleyck\d8177977\07	USER NAME = teasleyck 4449-sht-ATB.dgn	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>MONUMENTS &amp; TIES</b>			F.A.P. RTE. 827	SECTION •	COUNTY Wabash	TOTAL SHEETS 44	SHEET NO. 8
PLOT SCALE = 50.0000' / in.		CHECKED -	REVISED -					SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 74449	
PLOT DATE = 9/7/2011		DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
*(103,104)RS-1, (12)RS-2												