

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	100% STATE FUNDED CONSTRUCTION TYPE CODE				
				ROADWAY 0004	9TH ST BRIDGE 0011	ST. CLAIR BRIDGE 0014	LANDSCAPING 0031	TRAINEES 0042
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	132	132				
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50				
<del>20101700</del>	<del>SUPPLEMENTAL WATERING</del>	<del>UNIT</del>	<del>25</del>				<del>25</del>	
20200100	EARTH EXCAVATION	CU YD	42,850	42,850				
20800150	TRENCH BACKFILL	CU YD	1,925	1,925				
<del>21101015</del>	<del>TOPSOIL FURNISH AND PLACE, 4"</del>	<del>SQ YD</del>	<del>1,101</del>				<del>1,101</del>	
* 25000115	SEEDING, CLASS 1B	ACRE	6.25	6.25				
<del>* 25000240</del>	<del>SEEDING, CLASS 2A</del>	<del>ACRE</del>	<del>1.00</del>				<del>1.00</del>	
<del>* 25000305</del>	<del>SEEDING, CLASS 3A</del>	<del>ACRE</del>	<del>1.75</del>				<del>1.75</del>	
<del>* 25000342</del>	<del>SEEDING, CLASS 4A</del>	<del>ACRE</del>	<del>2.75</del>				<del>2.75</del>	
<del>* 25000344</del>	<del>SEEDING, CLASS 4B</del>	<del>ACRE</del>	<del>1.50</del>				<del>1.50</del>	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	551	551			<del>104</del>	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	551	551			<del>404</del>	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	551	551			<del>404</del>	
<del>* 25000775</del>	<del>SELECTIVE MOWING STAKES</del>	<del>EACH</del>	<del>28</del>				<del>28</del>	
* 25100115	MULCH, METHOD 2	ACRE	10.75	10.75				
<del>* 25100050</del>	<del>EROSION CONTROL BLANKET</del>	<del>SQ YD</del>	<del>30,720</del>				<del>30,720</del>	
<del>* 25200110</del>	<del>SOEDING, SALT TOLERANT</del>	<del>SQ YD</del>	<del>1,101</del>				<del>1,101</del>	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,684	2,684				
28000305	TEMPORARY DITCH CHECKS	FOOT	24	24				
28000400	PERIMETER EROSION BARRIER	FOOT	12,335	12,335				
28000500	INLET AND PIPE PROTECTION	EACH	60	60				
28100107	STONE RIPRAP, CLASS A4	SQ YD	164	164				
28200200	FILTER FABRIC	SQ YD	164	164				
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	2,271	2,271				
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	19,978	19,978				
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	2,262	2,262				
35300600	PORTLAND CEMENT CONCRETE BASE COURSE 11"	SQ YD	1,369	1,369				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11.9	11.9				
40600300	AGGREGATE (PRIME COAT)	TON	56.9	56.9				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	369	369				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	545	545				
40600990	TEMPORARY RAMP	SQ YD	256	256				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,477	1,477				

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	100% STATE FUNDED CONSTRUCTION TYPE CODE				
				ROADWAY 0004	9TH ST BRIDGE 0011	ST. CLAIR BRIDGE 0014	LANDSCAPING 0031	TRAINEES 0042
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,366	2,225		141		
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	9,137	9,137				
42001300	PROTECTIVE COAT	SQ YD	13,045	13,045				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	155	155				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	28,401	28,401				
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	339	339				
42400800	DETECTABLE WARNINGS	SQ FT	578	578				
44000100	PAVEMENT REMOVAL	SQ YD	23,156	23,156				
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	2,703	2,703				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7,379	7,379				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	395	395				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	577	577				
44000300	CURB REMOVAL	FOOT	2,704	2,704				
44000400	GUTTER REMOVAL	FOOT	440	440				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,472	9,472				
44000600	SIDEWALK REMOVAL	SQ FT	45,179	45,179				
44001980	CONCRETE BARRIER REMOVAL	FOOT	151	151				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	777	777				
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,963	1,963				
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	74	74				
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	765	765				
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	48	48				
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	156	156				
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	500	500				
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	336	336				
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	160	160				
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	10,250	10,250				
45200300	JOINT OR CRACK FILLING	POUND	2,975	2,975				
48100100	AGGREGATE SHOULDERS, TYPE A	TON	243	243				
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	308	308				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	163	163				
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	559	559				
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	1,059	1,059				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1				

FILE NAME = D8TR1-76C51-sht-summary-01-04.dgn

USER NAME = searsh  
 PLOT SCALE = 2.0000' / in.  
 PLOT DATE = MAR, 31, 2011

DESIGNED KM  
 DRAWN BS  
 CHECKED DBM  
 DATE 08/18/2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

\*SPECIALTY ITEM  
 STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 5 SHEETS STA. ----- TO STA. -----

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	82-1-3HB, 82-2N, 82-1-12RS	ST. CLAIR	352	5
	9166/9180/9213/9214			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		CONTRACT NO. 76C51	