

RESURFACING SCHEDULE

STATION LOCATION	35100700 AGGREGATE BASE COURSE, TYPE A, 8"	40200700 AGGREGATE SURFACE COURSE, TYPE A, 8"	40600115 POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40603230 POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, NSO	40603535 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NSO	44000100 PAVEMENT REMOVAL	48100700 AGGREGATE SHOULDERS, TYPE A, 8"
	SQ YD	SQ YD	GALLON	TON	TON	TON	SO YD	SO YD
VETERANS ROAD								
STA 10+12.00 TO STA 11+81.64 (PRIVATE ENTRANCE)		246						
STA. 26+81.57 TO STA. 33+13.50					372.7	225.4		
STA. 34+86.59 TO STA. 40+00.00					353.3	214.1		
STA. 26+81.57 TO STA. 33+13.50				2.0				
STA. 34+86.59 TO STA. 40+00.00				1.9				
STA. 26+81.57 TO EXISTING STRUCTURE							2251.7	
EXISTING STRUCTURE TO STA. 40+00.00							1797.4	
STA. 39+70.00 TO STA. 40+00.00								
STA. 26+81.57 TO STA. 33+13.50	2118							
STA. 34+86.59 TO STA. 40+00.00	2000							
STA 26+81.57 TO STA 33+10.51, RT								642.8
STA 26+81.57 TO STA 27+93.93, LT								131.5
STA 28+17.98 TO STA 33+19.23, LT								574.9
STA 34+80.19 TO STA 38+56.43, RT								482.2
STA 38+73.29 TO STA 40+00.00, RT								168.7
STA 34+90.09 TO STA 40+00.00, LT								506.6
STA. 27+81.57 TO STA. 33+13.50 (GRANULAR BASE)			1059.2					
STA. 34+86.59 TO STA. 40+00.00 (GRANULAR BASE)			1000.0					
STA. 26+81.57 TO STA. 33+13.50 (NEW BINDER)			61.4					
STA. 34+86.59 TO STA. 40+00.00 (NEW BINDER)			58.2					
TOTALS	4118	246	2179	4	726	440	4049	2507

CULVERT SCHEDULE

STATION LOCATION	50105220 PIPE CULVERT REMOVAL	542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"	542D1057 PIPE CULVERTS, CLASS D, TYPE 2 12"
		FT	FT
VETERANS RD			
STA. 37+50.00			
STA. 38+72.30		70.1	
STA. 38+67.60, LT TO STA. 38+76.42, RT	34		
PRIVATE ENTRANCE			
STA. 10+35.68			49.0

NOTE: ALL PIPE CULVERTS SHALL BE ALUMINIZED STEEL TYPE 2 CORRUGATED PIPE AS SPECIFIED IN ARTICLE 542.03 OF THE STANDARD SPECIFICATIONS.

EARTHWORK SCHEDULE

LOCATION	20200100 EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (30%)	EMBANKMENT	20400800 FURNISHED EXCAVATION WASTE(+)
	CU YD	CU YD	CU YD	CU YD
STAGE 1				
VETERANS	559.3	391.5	2237.5	-1846.0
PRIVATE ENTRANCE	6.1	4.3	43.1	-38.8
SUBTOTAL	565.4	395.8	2280.6	-1884.8
STAGE 2				
VETERANS	5077.8	3554.5	2523.1	1031.3
FARMDALE	9.8	6.9	94.1	-87.2
PRIVATE ENTRANCE	228.2	159.7	126.3	33.4
PLEASANT HILL RD	18.3	12.8	129.5	-116.7
SUBTOTAL	5334.2	3733.9	2873.1	860.8
TOTAL	5900			1885

54214077 ALUMINUM END SECTIONS 12"		
LOCATION	QUANTITY	UNIT
STA. 31+24.07, 36.1' LT	1	EACH
STA. 31+70.82, 36.2' LT	1	EACH
TOTAL	2	EACH

54214083 ALUMINUM END SECTIONS 18"		
LOCATION	QUANTITY	UNIT
STA. 37+50.00, 46.3' RT	1	EACH
STA. 37+50.00, 36.4' LT	1	EACH
STA. 38+63.32, 33.4' LT	1	EACH
STA. 38+81.50, 34.3' RT	1	EACH
TOTAL	4	EACH

MOBILIZATION SCHEDULE

STATION LOCATION	67100100 MOBILIZATION
	L SUM
ENTIRE PROJECT	1
TOTALS	1

GUARDRAIL/ROW MARKER SCHEDULE

STATION LOCATION	63000001 STEEL PLATE BEAM GUARDRAIL, 11'A 6FT POSTS	63100085 TRAFFIC BARRIER TERMINAL, TYPE 6	63100169 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	63200310 GUARDRAIL REMOVAL	66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	78200410 GUARDRAIL MARKERS, TYPE A	78201000 TERMINAL MARKER DIRECT APPLIED
	FOOT	EACH	EACH	FOOT	FOOT	EACH	EACH
VETERANS RD							
STA. 26+81.67, 40.0' RT					1		
STA. 26+81.67, 60.0' RT					1		
STA. 28+28.06, 60.0' RT					1		
STA. 28+75.17, 60.0' LT					1		
STA. 30+50.00, 60.0' LT					1		
STA. 30+50.00, 50.0' LT					1		
STA. 31+53.35, 60.0' RT					1		
STA. 31+53.35, 50.0' LT					1		
STA. 34+00.00, 60.0' RT					1		
STA. 34+66.06, 50.0' LT					1		
STA. 35+00.00, 45.0' RT					1		
STA. 35+50.00, 45.0' RT					1		
STA. 36+00.00, 40.0' RT					1		
STA. 36+25.00, 30.0' RT					1		
STA. 36+50.00, 30.0' RT					1		
STA. 36+83.84, 50.0' LT					1		
STA. 37+00.00, 40.0' RT					1		
STA. 39+00.00, 50.0' LT					1		
STA. 39+00.00, 40.0' LT					1		
STA. 39+00.00, 50.0' RT					1		
STA. 40+00.00, 50.0' RT					1		
STA. 40+00.00, 23.4' RT					1		
STA. 40+00.00, 40.0' LT					1		
STA. 40+00.00, 16.7' LT					1		
PLEASANT HILL RD							
STA. 8+89.91, 21.8' LT					1		
STA. 9+25.00, 18.2' RT					1		
STA. 9+25.00, 35.0' RT					1		
STA. 9+50.00, 50.0' LT					1		
STA. 9+60.00, 35.0' RT					1		
VETERANS RD							
STA. 33+29.06 TO STA. 33+98.31, LT				71.2			
STA. 33+36.86 TO STA. 34+04.65, LT				70.8			
STA. 34+75.93 TO STA. 34+94.28, LT				19.2			
STA. 34+83.18 TO STA. 35+04.99, LT				20.4			
STA. 35+08.26 TO STA. 37+02.50, RT	200.0						
STA. 32+80.37 TO STA 33+24.12, RT		1					
STA. 34+65.91 TO STA 35+08.26 RT		1					
STA. 32+90.34 TO STA 33+34.09, LT		1					
STA. 34+76.22 TO STA 35+21.45, LT		1					
STA. 32+30.70 TO STA. 32+80.37, RT			1				1
STA. 37+02.50 TO STA. 37+51.83, RT			1				1
STA. 32+40.68 TO STA. 32+90.34, LT			1				1
STA. 35+21.45 TO STA. 35+72.97, LT			1				1
STA 32+30.70 TO STA 33+24.12, RT						4	
STA 32+40.68 TO STA 33+34.09, LT						4	
STA 34+65.91 TO STA 37+51.83, RT						4	
STA 34+76.22 TO STA 35+72.97, LT						4	
TOTALS	200.0	4	4	182	29	16	4