



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 4, 2022

SUBJECT: FAP Route 404 (IL 40)
Project NHPP-16I9(181)
Section 50(BDR,BJR,BRR,L)
Peoria and Tazewell Counties
Contract No. 68F38
Item No. 28, November 18, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page 52 of the Special Provisions.
3. Revised sheets 8-24, 55, 132-136, 139-141, 147, 158, 177, 178, 185, 198-202, 205, 206, 209, 217, 218, 228, 229, 241, and 255 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

REMOVAL OF LIGHTING LUMINAIRE, SALVAGE

Description. This work shall consist of the removal of existing luminaires **and mast arms** in accordance with Section 842 of the Standard Specifications.

General. Where indicated in Peoria County, the luminaire and all associated hardware and appurtenances shall remain the property of the City of Peoria and shall be delivered by the Contractor to 3505 North Dries Lane, Peoria, Illinois, and unloaded and stacked there, as designated by the Engineer. Luminaires shall be removed and boxed in new containers, approved by the Engineer.

Where indicated on bridge structure or in Tazewell County, the luminaire and all associated hardware and appurtenances shall remain the property of the Department and shall be delivered by the Contractor to 6500 West US Route 150, Edwards, Illinois, and unloaded and stacked there, as designated by the Engineer. Luminaires shall be removed and boxed in new containers, approved by the Engineer.

Basis of Payment. This work will be paid for at the contract unit price Each for REMOVAL OF LIGHTING LUMINAIRE, SALVAGE.

SIDEWALK REMOVAL (SPECIAL) WITH PARAPET WALL

Description. This work shall consist of the removal and disposal of the existing cast in place concrete sidewalk with parapet wall in locations as shown in the plans or as directed by the Engineer.

Construction Requirements. All associated concrete, reinforcement bars, preformed joint filler, and embedded conduits shall be removed and disposed of by the Contractor. Removals shall be performed per the applicable portions of Article 501.05 of the Standard Specifications.

Care shall be taken not to damage the adjacent bridge deck and girders to remain in place. The Engineer shall be notified of any damage to the bridge deck or girders to remain and direction will be given on the repairs required. Any portion of the bridge deck or girders that is damaged by the Contractor's work shall be replaced to the satisfaction of the Engineer at the expense of the Contractor

Method of Measurement. Sidewalk Removal (Special) with Parapet Wall shall be measured for payment in place and the volume computed in Cubic Yards.

Basis of Payment. Removal of the existing moment slab will be paid for at the contract unit price per Cubic Yard for SIDEWALK REMOVAL (SPECIAL) WITH PARAPET WALL.

Revised November 4, 2022