

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0013 90% FED 10% STATE		
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	1111	1111		
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	267	267		
42000060	WELDED WIRE REINFORCEMENT	SO YD	1378	1378		
42000070	PAVEMENT CONNECTOR (HMA) FOR BRIDGE APPROACH SLAB	SO YD	144	144		
42001300	PROTECTIVE COAT	SO YD	1365	1365		
44000100	PAVEMENT REMOVAL	SO YD	144	144		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	802	802		
44004250	PAVED SHOULDER REMOVAL	SO YD	1378	1378		
50300100	FLOOR DRAINS	EACH	20	20		
50300225	CONCRETE STRUCTURES	CU YD	54	54		
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	227	227		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	90490	90490		
50800515	BAR SPLICERS	EACH	588	588		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0013 90% FED 10% STATE		
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	1800	1800		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70107007	PAVEMENT MARKING BLACKOUT TAPE, 7"	FOOT	2312	2312		
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9884	9884		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	4643	4643		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1050	1050		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	850	850		
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		

△ REVISED 11-2-2022 REV. - MS

MODEL: Default
 FILE: \\miller-pw-bentley.com\PWIDOT\Documents\DOT_Offices\District_7\Projects\74A70\CADD\Drawings\CAD\Sheets\74A70\Sheets\SOQ.dgn

USER NAME = Mona.Steffen	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/30/2022	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	D7 BRIDGE REPAIRS 2023-2	COLES	24	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74A70	

REV-SEP