

SUMMARY OF QUANTITIES - CONT

COUNTY:	WILLIAMSON	WILLIAMSON	WILLIAMSON	JACKSON
ROUTE:	FAP 331	FAP 331	FAP 331	FAP 331
FUNDING:	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
LOCATION:	URBAN	URBAN	RURAL	URBAN
	ROADWAY	TRAFFIC SIGNALS	ROADWAY	ROADWAY
	0003	0021	0005	0003

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0003	TRAFFIC SIGNALS 0021	RURAL ROADWAY 0005	URBAN ROADWAY 0003
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	360	360			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	234	234			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1		
* 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1		1		
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	36		36		
* 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	689		689		
* 81028720	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1" DIA.	FOOT	106		106		
* 81028750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	168		168		
* 81400100	HANDHOLE	EACH	7		7		
* 81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	936		936		
* 81603005	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	936		936		
* 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	890		890		
* 82110007	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION G	EACH	8		8		
* 82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	1		1		

* SPECIALTY ITEM

△ REVISED 11-1-2022

MODEL: 500
FILE: M:\11000-04\Bentley.com\PROJECTS\DOT\Office\District 9\Project\113\113.ctb; ahawnee\8172\113.ctb; 8/26/2022 10:50:00 AM

USER NAME = Sean.Greenlee	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 8/26/2022	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	**	-	272	15
CONTRACT NO. 78372			ILLINOIS FED. AID PROJECT	


**[1-4]R-4,N-6,TS-5;(5-3)W-1

JACKSON/WILLIAMSON

SUMMARY OF QUANTITIES - CONT

COUNTY:	WILLIAMSON	WILLIAMSON	WILLIAMSON	JACKSON
ROUTE:	FAP 331	FAP 331	FAP 331	FAP 331
FUNDING:	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
LOCATION:	URBAN	URBAN	RURAL	URBAN
	ROADWAY	TRAFFIC SIGNALS	ROADWAY	ROADWAY
	0003	0021	0005	0003

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0003	0021	0005	0003
* 82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1		1		
* 83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	4		4		
* 83600356	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8 5/8" X 6'	EACH	4		4		
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	16		16		
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1		
* 86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1		1		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,790		1,790		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,850		2,850		
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,440		1,440		
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	895		895		
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1		1		
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1		1		
* 87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	3		3		



* SPECIALTY ITEM

△ REVISED 11-1-2022

MODEL: 500
FILE: M:\GIS\p1\illdot\ca\benley.com\p1\illdot\Documents\DOT_Offices\District_9\Projects\113_giant_shawnee\8372\CADD\table\CA0\shades\09\8372_SMA-Cv_Inset_500_Sch.dgn

USER NAME = Sean.Greenlee	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/26/2022	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	**	-	272	16
			CONTRACT NO. 78372	
		ILLINOIS FED. AID PROJECT		

**[1-4]R-4,N-6,TS-5;(5-3)W-1

JACKSON/WILLIAMSON