



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

November 7, 2022

SUBJECT: FAU 2552 (Washington Street)
Section 16-00167-00-BR (Naperville)
DuPage County
Contract No. 61G82
Item 081
November 18, 2022 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices**
- 2. Revised Plan Sheets 27, 41, 186 & 190**
- 3. Added Plan Sheets 190A, 190B, & 190C**
- 4. Revised Special Provisions Table of Contents Page vi**
- 5. Added page 220A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TEMPORARY SUPPORT SYSTEM220A
LR107-04 FORM..... 221
LR1030-2 FORM..... 222
KANE/DUPAGE SOIL AND WATER CONSERVATION DISTRICT PERMIT..... 224
USACE 404 PERMIT..... 231
STORM WATER POLLUTION PREVENTION PLAN..... 241
IEPA NOTICE OF INTENT FOR GENERAL PERMIT..... 251
IEPA SEWER CONSTRUCTION PERMIT..... 254
IEPA WATER MAIN CONSTRUCTION PERMIT..... 256
DUPAGE COUNTY STORMWATER MANAGEMENT CERTIFICATION APPLICATION..... 258
IDNR/IDOT FLOODWAY PERMIT..... 261
LPC-663 FORM..... 269

TEMPORARY SUPPORT SYSTEM

Description:

This work shall consist of transporting to the site materials, furnishing all labor, tools, and equipment necessary to construct, install, and remove a temporary support system to support the damaged box beams as indicated on the plans or as directed by the Engineer, in accordance with the applicable portions of the Standard Specifications. The materials will be provided by the City of Naperville. Materials will be picked up by Contractor at the Department of Public Works yard, 180 Fort Hill Drive, Naperville, IL 60540.

General Requirements:

All portions of the temporary support system used by the Contractor, shall be identifiable and in good condition free of structural defects. The Engineer's approval will be required prior to installing the temporary support system. All items not approved by the Engineer shall be removed at the Contractor's Expense.

The Contractor shall be responsible for determining the appropriate equipment necessary to install the temporary support system according to the contract plans. The temporary support system shall be installed in accordance with the plans and special provisions prior to shifting traffic into Stage 1 configuration and commencing removal of the existing structure. The temporary support system shall be maintained until the damaged box beams are removed.

The temporary support system shall be removed and disposed of by the Contractor when Stage removal, per the plans, of the damaged box beams commences or when directed by the Engineer. The removed temporary support system shall become the property of the Contractor.

Contractor shall coordinate with City's resurfacing program's sub-contractor TCP/TSI (who installed temporary traffic control) as far as taking down of the latter's devices and the installation of the bridge subs devices.

Method of Measurement:

This work shall be measured for payment in units of LUMP SUM.

Basis of Payment:

This work will be paid for at the contract unit price lump sum for TEMPORARY SUPPORT SYSTEM at the locations as specified in the plans.

ADDED 10/27/2022