

SUMMARY OF QUANTITIES

SPLTY	SP	Code No.	Description	Unit	Total Quantity	Const. Type Code 80% Federal/20% Local				Const. Type Code 0% Federal/100% Local
						Reconstruction 0004 Urban	Traffic Signals 0021 Urban	Lighting 0021 Urban	Trainees 0042 Urban	Reconstruction 0004 Urban
~	*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	2,722		1,522	1200	1	
~	*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	0	1	0	1		
~	*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	170		170			
~	*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	670		670			
~	*	81028250	UNDERGROUND CONDUIT, GALVANIZED STEEL, 5" DIA.	FOOT	60		0	60	1	
~	*	81400100	HANDHOLE	EACH	11		11			
~	*	81400200	HEAVY-DUTY HANDHOLE	EACH	8		8			
~	*	81400300	DOUBLE HANDHOLE	EACH	5		5			
~	*	81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	10,000			10,000		
~		81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	50			50		
~		81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	361			361		
~	*	82110005	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION E	EACH	62			62		
~		82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240 VOLT, 100 AMP	EACH	1			1		
~	*	83000190	LIGHT POLE, ALUMINUM, 25 FT. M.H., 6 FT. DAVIT ARM	EACH	62			62		
~		83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6'	EACH	62			62		
~		83800506	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT OVER STAINLESS STEEL SCREEN	EACH	248			248		
~		84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	32			32		
~		84200804	REMOVAL OF POLE FOUNDATION	EACH	32		32			

1 REVISED SHEET 10/25/22

Drawing File: W:\Projects_by_Village\Maywood\56519231 - Washington Blvd - Ph (105-14_S000.dwg) Oct 25, 2022 - 3:47pm

HANCOCK ENGINEERING

100+ Years of Excellence

- ◆ Civil Engineers
- ◆ Municipal Consultants
- ◆ Established 1911

9933 Roosevelt Road
Westchester, IL 60154-2780
Phone: 708-865-0300
www.hancock.com

DESIGNED - SBC	REVISED -
DRAWN - SFB, DMM	REVISED -
CHECKED - WOP	REVISED -
DATE - 10-7-22	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. 5 OF 10 SHEETS	STA.	TO STA.

MUN RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1411	18-00139-00-PV	COOK	116	9
FIELD BOOK NO. : -		CONTRACT NO. 61J02		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

E.H.E. PROJECT NO. 565-19-23101