

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	(1) (2) EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) [EARTH EXCAVATION * 0.85] CU YD	(1) EMBANKMENT CU YD	(1) EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD	FURNISHED EXCAVATION CU YD	(3) (4) NON-SPECIAL WASTE DISPOSAL CU YD
		EXISTING TOPSOIL CU YD					
PEORIA STREET (SOUTH OF I-290) (3)	824	540	700	1,508	-808	808	
PEORIA STREET (NORTH OF I-290) (3)	201	42	171	0	171	0	
TOTAL	1,025	582	871	1,508		808	
NON-SPECIAL WASTE ADJUSTMENT (4)							
ADJUSTED TOTAL	1,025	582	871	1,508		808	

**NOTES:**

- (1) NOT A PAY ITEM
- (2) QUANTITIES FOR EARTH EXCAVATION AVAILABLE FOR EMBANKMENT HAVE NOT BEEN ADJUSTED TO EXCLUDE ANY VOLUME OF CONTAMINATED EARTH EXCAVATION REQUIRING DISPOSAL AS NON-SPECIAL WASTE.
- (3) ACTUAL VOLUMES OF NON-SPECIAL WASTE SHALL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION. NO ESTIMATED QUANTITY ADJUSTMENTS HAVE BEEN APPLIED.
- (4) A QUANTITY HAS NOT BEEN DETERMINED FOR NON-SPECIAL WASTE DISPOSAL BASED ON THE PRELIMINARY SOIL INVESTIGATION LOCATIONS. SEE SPECIAL PROVISIONS REGARDING LOCATIONS AND REQUIREMENTS FOR PROPER HANDLING AND DISPOSAL.

FILE PATH = p:\388035\pmt\escomon\me\local\p\AECD\00\Documents\01\_Americas\Transportation\60269938\_Circle\Phase\_1\1\000\_CAD\006\_Roadway\_Sheets\60X62\_Contract\0160X62-sht-GRADING-SCHEDULE.dgn



DI60X62-sht-GRADING-SCHEDULE.dgn	DESIGNED - JLV	REVISED -
USER NAME = BAWtor t	DRAWN - BAW	REVISED -
PLOT SCALE = 40.0000' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 8/19/2014	DATE - 8/20/2014	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**GRADING, DRAINAGE AND UTILITY PLAN  
SCHEDULE**

SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-074I	COOK	58	24
CONTRACT NO. 60X62			ILLINOIS FED. AID PROJECT	