

IRRIGATION GENERAL NOTES

1. CONTACT ALL UTILITIES AND GENERAL CONTRACTOR AT LEAST 5 DAYS PRIOR TO THE START OF CONSTRUCTION.
2. MAINTAIN ALL CODES REQUIRED BY STATE AND LOCAL AUTHORITIES.
3. COORDINATE ALL SLEEVES AND PENETRATIONS WITH GENERAL CONTRACTOR. IRRIGATION CONTRACTOR IS RESPONSIBLE FOR BORES, SLEEVES OR PENETRATIONS RELATED TO THE IRRIGATION.
4. IRRIGATION HEADS AND LINES ARE SCHEMATIC - MINOR FIELD ADJUSTMENTS MAY BE REQUIRED.
5. INSTALL ALL PIPING AND FITTINGS USING GLUE METHODS CONSISTANT WITH MANUFACTURER'S RECOMMENDATIONS.
6. MAINLINE PIPING SHALL BE INSTALLED AT MINIMUM OF 12" LATERAL LINES SHALL BE INSTALLED AT A MINIMUM DEPTH OF 12".
7. CAP OR PLUG ALL OPENINGS AS SOON AS LINES ARE INSTALLED TO PREVENT DEBRIS IN THE LINE.
8. THOROUGHLY FLUSH ALL LINES PRIOR TO THE OPERATION OF SPRINKLER HEADS.
9. INSTALL WIRES A MIN. OF 10" BELOW GRADE.
 - a. SPLICES ARE NOT ALLOWED IN THE TRENCH.
 - b. PROVIDE A 24" EXPANSION LOOP AT EACH CHANGE IN DIRECTION.
 - c. 5 FEET OF EXCESS DECODER WIRE IS TO BE AT EACH DECODER LOCATION FOR EASE OF ACCESS.
10. THE IRRIGATION SYSTEM SHALL BE TESTED AT OPERATING PRESSURE FOR A MINIMUM OF 4 HOURS. REPAIR ALL LEAKS AND RETEST AFTER CURING.
11. UPON COMPLETION OF TEST, COMPLETE ASSEMBLY OF ALL EQUIPMENT AND SPRINKLERS FOR PROPER DISTRIBUTION.
12. PROVIDE 'AS BUILT' DRAWINGS SHOWING ALL COMPONENTS OF THE SYTEM PRIOR TO FINAL PAYMENT. PROVIDE FINAL GPM OF ZONES, WIRE RUNS, HEADS, VALVES, PIPE SIZES ETC.
13. ALL GASKETED PRESSURE PIPE AND FITTINGS SHALL BE THRUST BLOCKED. NO CONCRETE PREFORMED BLOCKS WILL BE ALLOWED.
14. ALL EXISTING UTILITIES WHICH ARE NOT SHOWN ON THESE DOCUMENTS WHICH NEED TO BE REMOVED, RELOCATED AND/OR ADJUSTED SHALL BE THE RESPONSIBILITY OF THE IRRIGATION CONTRACTOR.
15. ALL BIDDERS SHALL VISIT AND REVIEW THE SITE AND FAMILIAR THEMSELVES WITH THE SITE THE SITE PRIOR TO SUBMITTING A BID.
16. CONTRACTOR IS RESPONSIBLE FOR SUBMITTING AND ACQUIRING ALL PERMITS.
17. PRIOR TO INSTALLATION, FIELD TEST THE SYSTEM PRESSURE AT THE POINT OF CONNECTION. CONTRACTOR IS RESPONSIBLE TO VERIFY THE PRESSURE IS AT LEAST 45 STATIC PSI; NOTIFY OWNER IF PRESSURE IS LOWER.
18. DRAWING IS SCHEMATIC, FIELD ADJUSTMENTS MAY BE NEEDED. LOCATE ALL MAIN LINES AND LATERAL LINES IN TURF OR PLANTING AREAS. COMPONENTS ARE DRAWN OUTSIDE OF AREAS FOR EASE OF READING.

FILE PATH = p:\388039\pmt\escomon\me\local\p\AECD\00\Documents\01_Americas\Transportation\60269938_Circle\Phase_1\000_CAD\006_Roadway\Sheets\60X62_Contract\0160X62-Sht-IRRIGATION-DET-01.dgn

	D160X62-Sht-IRRIGATION-DET-01.dgn	DESIGNED - JLJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IRRIGATION PLAN GENERAL NOTES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	USER NAME = BAWtor t	DRAWN - BAW	REVISED -			90/94/290	2013-074I	COOK	58	36
PLOT SCALE = 40.0000' / in.	CHECKED - JMG	REVISED -	CONTRACT NO. 60X62							
PLOT DATE = 8/19/2014	DATE - 8/20/2014	REVISED -	ILLINOIS FED. AID PROJECT							
		SCALE: NONE			SHEET 1 OF 1 SHEETS STA. TO STA.					