INDEX OF SHEETS

SHEET NO.	DESCRIPTION						
***	TITLE SHEET						
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES						
3	SUMMARY OF QUANTITIES						
4	SCHEDULE OF QUANTITIES						
5 - 11	LOCATION MAPS						
12	EXISTING BRIDGE PLANS (LOCATION NO 1, SN 049-0001)						
13	EXISTING BRIDGE PLANS (LOCATION NO 2, SN 049-0002)						
14	EXISTING BRIDGE PLANS (LOCATION NO 3, SN 049-0011)						
15	EXISTING BRIDGE PLANS (LOCATION NO 4, SN 049-0012)						
16	EXISTING BRIDGE PLANS (LOCATION NO 5, SN 049-0037)						
17	EXISTING BRIDGE PLANS (LOCATION NO 6, SN 049-0039)						
18	EXISTING BRIDGE PLANS (LOCATION NO 7. SN 049-0068)						
19	EXISTING BRIDGE PLANS (LOCATION NO 8, SN 049-0079)						
20	EXISTING BRIDGE PLANS (LOCATION NO 9, SN 049-0081)						
21	EXISTING BRIDGE PLANS (LOCATION NO 10, SN 049-0082)						
22	EXISTING BRIDGE PLANS (LOCATION NO 11, SN 049-0083)						
23	EXISTING BRIDGE PLANS (LOCATION NO 12, SN 049-0088)						
24	EXISTING BRIDGE PLANS (LOCATION NO 13, SN 049-0131)						
25	EXISTING BRIDGE PLANS (LOCATION NO 14, SN 049-0152)						
26	EXISTING BRIDGE PLANS (LOCATION NO 15. SN 049-0153)						
27	EXISTING BRIDGE PLANS (LOCATION NO 16, SN 049-0156)						
28	EXISTING BRIDGE PLANS (LOCATION NO 17, SN 049-0165)						
29	EXISTING BRIDGE PLANS (LOCATION NO 18, SN 049-0166)						
30	EXISTING BRIDGE PLANS (LOCATION NO 19, SN 049-0169)						
31	EXISTING BRIDGE PLANS (LOCATION NO 20, SN 049-0176)						
32	EXISTING BRIDGE PLANS (LOCATION NO 21, SN 049-0177)						
33	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0187)						
34	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0191)						
36	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0193)						
36	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0194)						
37	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0200)						
38	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0208)						
39	EXISTING BRIDGE PLANS (LOCATION NO 22, SN 049-0212)						
40	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS. INTERSECTIONS, AND DRIVEWAYS (TC-10)						
41	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14)						
42	ARTERIAL ROAD INFORMATION SIGN (TC-22)						

LIST OF STATE STANDARDS

SIANDARD NO.	DESCRIPTION
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701502-06	URBAN LANE CLOSURE, 2L, 2W, WITH BIDIRECTIONAL LEFT TURN LANE
701601-09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701606-09	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-09	URBAN LANE CLOSURE MULTILANE INTERSECTION
701801-05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-03	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 1-800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC. TELEPHONE AND GAS FACILITIES. 48 HOURS NOTIFICATION IS REQUIRED.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF NORTH CHICAGO, LAKE FOREST AND IN THE VILLAGE OF LAKE VILLA, LINCOLNSHIRE, LAKE FOREST, METTAWA, BARRINGTON HILLS, LAKE BARRINGTON, HIGHLAND PARK, LAKE BLUFF, LIBERTYVILLE, FOX RIVER GROVE, NORTH BARRINGTON, LINCOLNSHIRE, VERNON HILLS, LONG GROVE AND BUFFALO GROVE.

THE CONTRACTOR SHALL TAKE NECESSARY PRECAUTIONS TO INSURE THAT NO DEBRIS WILL ENDANGER OR INTERFERE WITH TRAFFIC ON THE ROADWAY (OR THE RAILROAD) BENEATH THE BRIDGE ACCORDING TO ARTICLE 107.09 (OR 107.12) OF THE STANDARD SPECIFICATIONS. THIS WORK WILL NOT BE PAID FOR SEPERATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE APPROPRIATE PAY ITEM INVOLVED AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE RESIDENT ENGINEER SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470. A MINIMUM OF 72 HOURS PRIOR TO THE INSTALLATION OF ANY TEMPORARY TRAFFIC CONTROL DEVICES

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS

FILE NAME :	USER NAME = ababa-a	DESIGNED -	REVISED -
c1\p+,,+ork\p+tdot\ab#bavo\d0402136\0135	IA-Designidgn	DRAWN -	REVISED -
	PLOT SCALE . 100.8000 1/ 10.	CHECKED -	REVISED -
Default	PLOT DATE . 0/10/2014	DATE -	REVISED -

STATE OF ILLINOIS				
DEPARTMENT	OF	TRANSPORTATION		

						SECTION COUNTY TOTAL SHE			SHEET NO.		
	INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES							2014-0401	LAKE	42	2
1	· · · · · · · · · · · · · · · · · · ·	,							CONTRACT	NO. 60	3Y34
1	SCALE:	SHEET	OF	SHEETS	STA,	TO STA.		ILLINOIS FED. A	D PROJECT		