SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0014					
CODE NO	ITEM	UNIT		0014					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
* 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3					
* 70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1					
* X0327186	PORTABLE VIDEO TOWER STATIONS	CAL MO	3	3					
1 X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
* X7010410	SPEED DISPLAY TRAILER	CAL MO	3	3					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
* X8570000	SMART TRAFFIC MONITORING SYSTEM	L SUM	1	1					
Z0001905	STRUCTURAL STEEL REPAIR	POUND	18,590	18,590					
~~Z0021910~~	~~SILICONE JOINT SEALER, 2.25"~~	~~FOOT~~	~~8~~	~~8~~					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52.4	52.4					
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	31	31					
Z0021907	SILICONE JOINT SEALER, 1 3/4"	FOOT	23	23					
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	117	117					
Z0021914	SILICONE JOINT SEALER, 2 3/4"	FOOT	206	206					

1 * SPECIALTY ITEMS

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

Rev.

FILE NAME =	USER NAME = Gorangoo100	DESIGNED -	REVISED -
c:\pw_work\pwidot\gorangoo100\d0404050\D44SM-sht-dsgnl.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 9/8/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-80 OVER DESPLAINES RIVER
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99-3-BR-2	WILL	57	3
		CONTRACT NO. 60Y64		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

1 Rev. 11-6-14